

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-23052-00-00
Spot: NWNESE Sec/Twnshp/Rge: 32-9S-21W
2630 feet from S Section Line, 800 feet from E Section Line
Lease Name: DE YOUNG Well #: 1
County: GRAHAM Total Vertical Depth: 3948 feet

Operator License No.: 32016
Op Name: WELLS, RODGER D. DBA PIONEER RES
Address: 90 WINDMILL DR.
PHILLIPSBURG, KS 67661

String	Size	Depth (ft)	Pulled (ft)	Comment
PC		1810		375 SX CMT 128.31
PROD	5.5	3947	0	150 SX CMT ASC 2% GEL
SURF	8.625	251	0	175 SX CMT 60/40 POZ 2% GEL, 3% CC
T1	2.875	3921		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/06/2009 11:00 AM
Plug Co. License No.: 34115 Plug Co. Name: SCHIPPERS OILFIELD SERVICES, LLC
Proposal Rcvd. from: ROGER WELLS Company: PIONEER RESOURCES Phone: (785) 543-5556

Proposed Plugging Method: Ordered out 300 sxs 60/40 pozmix - 4% gel - 500# hulls - 14 sxs gel spacer.
PC at 1809' w/375 sxs cwc.

Plugging Proposal Received By: BRUCE BASYE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/06/2009 5:30 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran tubing to 3700'. S.O.S. pumped 14 sxs gel spacer - followed with 70 sxs 60/40 pozmix - 4% gel with 200# hulls.
Pulled tubing to 1800'. S.O.S. pumped 160 sxs cement with 300# hulls.
PTOH. Squeezed 40 sxs cement.
Max. P.S.I. 450#. S.I.P. 450#.
Backside full of cement. ALT II.

Perfs:

Top	Bot	Thru	Comments
3915	3919		
INVOICED DATE <u>2-19-09</u> INV. NO. <u>2009061238</u>			
RECEIVED KANSAS CORPORATION COMMISSION FEB 17 2009 CONSERVATION DIVISION WICHITA, KS			

Remarks: SOS CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed

Richard Williams

(TECHNICIAN)

CM

Form CP-2/3

FEB 11 2009

PBT