

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-21801-00-02  
Spot: SENWSW Sec/Twnshp/Rge: 30-10S-24W  
1624 feet from S Section Line, 4276 feet from E Section Line  
Lease Name: GANO Well #: 1-B  
County: GRAHAM Total Vertical Depth: 4300 feet

Operator License No.: 6861  
Op Name: RON'S OIL OPERATIONS INC.  
Address: 1889 200TH AVE  
PENOKEE, KS 67659

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	1938	0	w/unknown sxs cmt
SURF	8.625	298	0	w/175 sxs cmt <u>139.75</u>

Well Type: SWD UIC Docket No: D27967.0 Date/Time to Plug: 02/09/2009 10:30 AM  
Plug Co. License No.: 3152 Plug Co. Name: POE SERVICING INC  
Proposal Rcvd. from: RONALD NICKELSON Company: RON'S OIL OPERATIONS INC. Phone: (785) 421-8800

Proposed Plugging Method: Ordered 225 sxs 60/40 pozmix - 4% gel - 700# hulls.  
Plugged off bottom w/125 sxs cement and 500# hulls in 1987.  
PBTB 1836'.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 02/09/2009 12:45 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Poe Well Service RIH to 1650'. SOS rigged to tubing - pumped 150 sxs 60/40 pozmix - 4% gel with 500# hulls to circulate cement to pit area.  
Pulled tubing - rigged to 4 1/2" casing with a swedge - pumped 50 sxs 60/40 pozmix - 4% gel.  
Max. P.S.I. 500#. S.I.P. 500#.  
Note: 8 5/8" had cement visible around pipe.

Perfs:


Top	Bot	Thru	Comments
1800	1884		
<b>VOICED</b> DATE <u>2-19-09</u> NO. <u>2009061241</u>			
RECEIVED KANSAS CORPORATION COMMISSION <b>FEB 12 2009</b> CONSERVATION DIVISION WICHITA, KS			

Remarks: S.O.S. SCHIPPERS CEMENTING COMPANY-TICKET #331.

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

CM

Form CP-2/3

FEB 10 2009



RON'S OIL OPERATIONS  
PENOKEE KS 67659

30-10S-24W  
1600' FSL & 930' FWL, SEC

#1-B GANO OWWO

site 2-1/2 S & 1-3/4 E OF ST PETER KS

city GRAHAM

API 15-065-21801-B

contr: UNKNOWN

field: MARTHA WASHINGTON SE


geol:  
fr date 12/01/2000    spd date 11/09/2001    drg comp 11/09/2001    card issued 04/08/2002    last revised 10/06/2003

ELV: 2483 KB, 2478' GL LOG	tops.....	depth/datum
ANH.....	2141	+342
B/ANH.....	2174	+309
HEEB.....	3784	-1301
TOR.....	3804	-1321
LANS.....	3819	-1336
BKC.....	3865	-1382
MARM.....	4093	-1610
FT SC.....	4255	-1772
CHER.....	4275	-1792
RTD OLD.....	4300	-1817
LTD OLD.....	4301	-1818

IP status:

SWDW, CED HILL 1700-1884, 01/08/2002  
 INFO REL: 10/6/2003 - WAS SWDW - TIGHT HOLE  
 NOTE CORR 12/1/2000 - ORIG FR IN SE NW SW  
 OLD INFO: OPERATOR WAS ABERCROMBIE DRILLING,  
 1-B GANO, SPD 05/28/1983, 06/06/1983 8-5/8" 298 / 175 SX  
 (ALT 2), D&A, CHER, 06/06/1983(CARD ISSUED 08/11/1983)  
 CONTR: ABERCROMBIE DRILLING  
 NO CORES  
 DST (1) 3836-3858 (LANS), / 30-45-60-45, 180' GIP, REC 180'  
 OCM, 496' MC GSY OIL (15% OIL), 310' WTRY OIL (50%  
 OIL, 45% W), 310' OCW (12% OIL), 868' CLEAN SW ISIP  
 1196# FSIP 1180# IFP 170# -568# FFP 625# -968#

COPYRIGHT 2003  
INDEPENDENT OIL & GAS SERVICE, INC.  
WICHITA, KANSAS

(over)

RON'S OIL OPERATIONS  
PENOKEE KS 67659

30-10S-24W  
1600' FSL & 930' FWL, SEC

#1-B GANO OWWO

DST (2) 3936-3969 (PLEAS), / 30-45-30-45, REC 25' M ISIP 477# FSIP 227# IFP 34# -34# FFP 34# -34#  
 DST (3) 3973-3992 (PLEAS), / 30-30-30-30, REC 20' M, NS ISIP 56# FSIP 34# IFP 27# -27# FFP 27# -27#  
 DST (4) 3992-4016 (PLEAS), / 30-45-30-45, REC 30' M, W/FEW OIL SPTS ISIP 685# FSIP 372# IFP 22#  
 -22# FFP 29# -29#  
 DST (5) 4207-4301 (FT SC, CHER), / 30-45-30-45, REC 40' M ISIP 170# FSIP 125# IFP 102# -113# FFP  
 113# -113#

1 WORKOVER:

OPERATOR WAS RON'S OIL OPERATIONS #1-B GANO OWWO RE-ENTERED 11/01/1987, 11/01/1987  
 WSH DWN TO 4300PROD CSG NA, INJ, LKC, INTV NA, 12/01/1987(CARD ISSUED 12/16/1987)  
 CONTR: UNKNOWN  
 GEOL: NONE  
 MICT - CO, FF (LKC) INTV NA, AC'D, COMP AS WIW - INJECTION RATE SATISFACTORY, 12/1/1987  
 (WELL P & A - DATE NA) - NO OTHER INFO AVAILABLE  
 NEW INFO: FR 12/01/2000, RE-ENTERED 11/09/2001 WSH DWN TO 1900 DC 11/09/2001 CSG: PROD  
 CSG ALREADY IN HOLE  
 COMMENT: WAS ABD OWWO, CANCELLED PERMIT (FR 4/29/1986, RON'S OIL OPER; WAS KCC API  
 15-065-21801-0001); PERMIT EXTENDED 6/1/2001  
 TRGT ZN: CED HILL (SWDW), PTD 1900 (CED HILL), MICT - CO, FF (CED HILL) 1700-1884, COMP AS  
 SWDW - INJECTION RATE SATISFACTORY, 1/8/2002