

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-20717-00-00
Spot: NENWNW Sec/Twnshp/Rge: 22-25S-5E
4959 feet from S Section Line, 4278 feet from E Section Line
Lease Name: KNOX A Well #: 50
County: BUTLER Total Vertical Depth: 2565 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 1700 WATERFRONT PKWY BLDG 500
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		2130		
CIBP		2385		
PROD	5.5	2564	350 SX	83.3Le
SURF	8.625	219	150 SX	

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/16/2009 8:00 AM
Plug Co. License No.: 32991 Plug Co. Name: SIMMONS WELL SERVICE, INC.
Proposal Rcvd. from: CASEY COATS Company: VESS OIL CORPORATION Phone: (316) 655-1997

Proposed Plugging Method: PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 01/16/2009 12:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/WORKSTRING @ 1,945', CONSOLIDATED MIXED & PUMPED 50 SXS CLASS A 3% CC AND DISPLACED IN CASING. WAITED 2 HOURS, TAGGED CEMENT @ 1/601'. PRESSURED CASING @ 300#, HELD OK. RIH WW/WORKSTRING @ 280', ESTABLISHED CIRCULATION, CONSOLIDATED MIXED & PUMPED 40 SXS CLASS A CEMENT TO SURFACE. CEMENT CIRCULATED. CONSOLIDATED TICKET #20510.

Perfs:

Top	Bot	Thru	Comments
2522	2524		ARBUCKLE
2500	2504		SIMPSON
2188	2212		HEPLER
1954	1960		KC

INVOICED

DATE 2-19-09

INV. NO. 2009061244

RECEIVED
KANSAS CORPORATION COMMISSION

FEB 13 2009

CONSERVATION DIVISION
WICHITA, KS

Remarks: RETAINER @ 2523' / 6/75 CMT BETWEEN 5-1/2" & 8-5/8" / SQUEEZED LEAKS @ 510-543, 901-1040.

Plugged through: TBG

District: 02

Signed

Duane Krueger
(TECHNICIAN)

PBT