

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-21115-00-01
Spot: SESWSWSE Sec/Twnshp/Rge: 28-25S-5E
43 feet from S Section Line, 2095 feet from E Section Line
Lease Name: HEGBERG A Well #: 194
County: BUTLER Total Vertical Depth: 2150 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 1700 WATERFRONT PKWY BLDG 500
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	2150		175 SX
SURF	8.625	254		175 SX

69.88

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/27/2009 8:00 AM
Plug Co. License No.: 32991 Plug Co. Name: SIMMONS WELL SERVICE, INC.
Proposal Rcvd. from: CASEY COATS Company: VESS OIL CORPORATION Phone: (316) 655-1997

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 01/27/2009 2:45 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TBG @ 1,698, CONSOLIDATED OIL WELL SERVICES MIXED & PUMPED 75 SXS CLASS A 3% CC AND DISPLACED IN CASING. WAITED 2 HRS, TAGGED CEMENT @ 1178', PRESSURED CASING @ 200#, HELD OK. RIH W/TBG @ 310', CONSOLIDATED ESTABLISHED CIRCULATION AND MIXED & PUMPED 45 SXS CLASS A CEMENT TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 1/27/2009, 2:45 P.M. WHILE DRILLING WELL BACK OUT, OPERATOR HAD HOLE IN CASING @ 1722, 628'-644' SQZD 200 SXS, 789' CIRC. CMT TO SURFACE, 15 SXS 1720'-24', 1726'-30', 1980'-84', 1996'-2004'.

Perfs:

Top	Bot	Thru	Comments
1996	2004		
1980	1984		
1726	1730		
1720	1724		

INVOICED

DATE 2-19-09
INV NO. 2009061244

RECEIVED
KANSAS CORPORATION COMMISSION
FEB 13 2009
CONSERVATION DIVISION
WICHITA, KS

Remarks: CONDOLIDATED CEMENT TICKET #20537.

Plugged through: TBG

District: 02

Signed *Duane Krueger*
(TECHNICIAN)

PKT