

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-01322-00-00  
Spot: SENENE Sec/Twnshp/Rge: 18-7S-20W  
4290 feet from S Section Line, 330 feet from E Section Line  
Lease Name: LASAGE Well #: 3  
County: ROOKS Total Vertical Depth: 3587 feet

Operator License No.: 33723  
Op Name: PAUL BOWMAN OIL TRUST  
Address: 801 CODELL RD  
CODELL, KS 67663

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3586	0	200 SX
SURF	8.625	183	0	150 SX
T1		3010		

Well Type: OIL UIC Docket No: Paul Bowman Oil Trust Date/Time to Plug: 02/05/2009 11:00 AM  
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS  
33723 COMPANY TOOLS  
Proposal Rcvd. from: LOUIS "DON" BOWMAN Company: PAUL BOWMAN OIL TRUST Phone: (785) 434-2286

Proposed Plugging Method: Ordered 450 sxs 60/40 pozmix - 4% gel - 2% cc - 600# hulls.  
Perforate at 1700' - 1050' - 150'.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 02/05/2009 2:00 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 2950' - pumped 100 sxs 60/40 pozmix - 4% gel - followed with 75 sxs 60/40 pozmix - 4% gel and 100# hulls - 2% c.c. - had circulation.  
Pulled tubing 1690' - pumped 20 sxs 60/40 pozmix - 4% gel - 2% c.c. to circulate to surface.  
Pulled all tubing - pumped 20 sxs 60/40 pozmix - 4% gel - 2% c.c. to top off 4 1/2" casing.  
Hooked to backside - pumped 10 sxs 60/40 pozmix - 4% gel - 2% c.c. - circulated around to 4 1/2" casing.

Perfs:

INVOICED  
DATE 2-19-09  
INV NO. 2009061236

RECEIVED  
KANSAS CORPORATION COMMISSION  
FEB 12 2009  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY-TICKET #34940.

Plugged through: TBG

District: 04

Signed Pat Bedore  
(TECHNICIAN) CM

FEB 10 2009

PK

IMPERIAL OIL

#3

LE SAGE

18-7-20W

SE NE NE

Contr. IMPERIAL OIL

ROOKS

County

E 2106 RB Comm

Comp. 1-6-61

IP

150 BOPD

Tops	Depth	Datum
HEEB	3290	-1184
TOR	3311	-1205
LANS	3329	-1223
ARB	3557	-1451
TD	3587	-1481

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS

Casing:

8" 183

5" 3586

DST 3352-73/30", 10' M, BHP 1220-1180#: DST  
3372-92/30", 10' M, BHP 0#: DST 3391-3405/30"  
10' M, BHP 0#: DST 3405-15/2 HR, 60' C, 90'  
OCM, 60' H OCM, BHP 1150-1170#: DST 3492-3510  
/2 HR, 130' H OCM, 60' MDY O, BHP 1100-950#  
DST 3508-50/105", 65' OCM, BHP 650-110#  
DST 3559-66/2 HR, 110' OCM, BHP 970-470#  
DST 3566-87/2 HR, 255' V H OCM, BHP 850-  
300": PERF 40/3570-80: SWB 1/2 BOPH, NATL/  
2 HR: ACID 1000: SWB 2 1/2 BOPH: FRAC: SWB 5  
BOPH/6 HR: 20/3505-09: 3 BOPH, NATL: ACID  
LE SAGE POOL  
3500: 6 1/4 BOPH/5 HRS:  
12/3515-18: ACID 500:  
1 1/4 BOPH/4 HRS: 16/3406-  
10: DRY: ACID 500: RE-  
PERF 3410-15: 3 1/4 BOPH/  
5 HRS

+	+	+
+	+	+
+	+	+