

12-29 15-195-21316-00-00

6 031215

API NUMBER 15-

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

NE NW SW, SEC. 18, T 11 S, R 21 W/E  
2310 feet from S section line

TECHNICIAN'S PLUGGING REPORT

Operator License #6039

Lease Name Lynd A Well # 1

Operator: L.D. Drilling Inc.

Name & Address R. R. 1 Box 183 B  
Great Bend, Ks. 67530

County Trego 127.24

Well Total Depth 3915 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 215

Abandoned Oil Well  Gas Well  Input Well  SWD Well  U&A

Other well as hereinafter indicated

Plugging Contractor Allied Cement Co. License Number

Address Russell, Ks.

Company to plug at: Hour: AM Day: 29 Month: Dec Year: 19 88

Plugging proposal received from Pete Fiorini

(company name) L.D. Drilling Inc. (phone)

were: 8 5/8" set at 215' w/cwc sks. 5 1/2" set at 3913' w/200 sks. PBD 3893'.

Perf 3864' - 3880'. Shots at 1733' and below Dakota at 940'. Pulled pipe. Order sand

and common cement. Pull pipe. Order 200 sks 65/35 Poz 10% Gel 2% Dicel 500# Hulls.

Allied Cement Co. Wellbrock Water Truck. Run wireline to anhy.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 11:30AM Day: 29 Month: Dec Year: 19 88

ACTUAL PLUGGING REPORT Sand bottom to 3800' w/5 sks cement on sand w/bailer.

Shots at 1733' anhy and 940'. Recovered 940' of 5 1/2" casing. Squeezed 8 5/8" w/200

sks cement w/5 sks Hulls mixed into max psi 1000#. Close in psi 150#. Plug complete.

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED  
DATE 1-19-89  
INV. NO. 23708  
12-29

Signed Carl Goodrow (TECHNICIAN)

Carl Goodrow