

15-195-22062-00-00

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-22062-00-00
Spot: N2N2SW Sec/Twnshp/Rge: 18-11S-21W
2310 feet from S Section Line, 3960 feet from E Section Line
Lease/Unit Name: LYND Well Number: 1
County: TREGO Total Vertical Depth: 3870 feet

Operator License No.: 3194
Op Name: TRI UNITED, INC
Address: 950 270TH AVE
HAYS, KS 67601

Conductor Pipe: Size feet: 8/25.78
Surface Casing: Size 8.625 feet: 307 185 SXC MT
Production: Size 4.5 feet: 3870 200 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 09/04/2002 11:00 AM
Plug Co. License No.: 3194 Plug Co. Name: TRI UNITED, INC
Proposal Rcvd. from: EUGENE E. LEIKER Company: TRI UNITED, INC Phone: (785) 628-3670

Proposed Plugging Method: According to Kansas Corporation Commission Rules & Regulations.
Ordered 210 sxs cement and 500# hulls.

Plugging Proposal Received By: HERB DEINES Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 09/04/2002 12:30 PM KCC Agent: ROGER MOSES

Actual Plugging Report:

8 5/8" S.P. at 307' w/185 sxs cement. 4 1/2" casing at 3870' w/200 sxs cement.
Tied to 4 1/2" casing and squeezed 200 sxs cement and 500# hulls.
Max. P.S.I. 1000#. S.I.P. 1000#.
Tied to 8 5/8" x 4 1/2" annulus and pressured to 500# immediately - took no cement.
Total of 200 sxs 60/40 pozmix - 10% gel and 500# hulls.

9-23-2002
SEP 23 2002

KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY. TRI-UNITED-WATER.

Plugged through: CSG

District: 04

Signed Roger L. Moses
(TECHNICIAN)

INVOICED

Form CP-2/3

9-17-2002
SEP 17 2002

DATE 9-24-02
INV. NO. 2003060549

LANSING

STATE KANS COUNTY TREGO
 FIELD STRATON (MARMATON)
 OPER LANSING ENERGY/LINCOLN OIL
 WELL 1 LYND
 API 15-195-22062-0000
 SPUD 10/31/1990
 DTD 3870

9807

WELL CLASS 2310FSL 3960FEL SEC
 STATUS DO
 COMP OIL
 PBTD 12/01/1990
 3668

18-11S-21W
 N2 N2 SW

+	+	+	+	+	+	+	+
+	+	+	+	+	+	+	+
+	+	+	+	+	+	+	+
+	+	+	+	+	+	+	+
+	+	+	+	+	+	+	+
+	+	+	+	+	+	+	+
+	+	+	+	+	+	+	+
+	+	+	+	+	+	+	+

LOC 7 1/2 MI NE OGALLAH, KS

Petroleum Information Corporation

IP IPP 25 BOPD 55 BW GTY 36
 PROD ZONE: MARMATON 3847-3852

EL: 2235 KB 2230 GR

CSGS: 8 5/8 @ 307 W/ 185 SACKS
 4 1/2 @ 3870 W/ 200 SACKS
 TBGS: 2 3/8 @ 3842
 DRLG COMP 11/4/90 RIG REL 11/4/90

LOG TOPS:
 STONE CORRAL AN 1686 +549
 HEEBNER 3497 -1262
 LANSING 3535 -1300
 BSE KANSAS CITY 3764 -1529
 MARMATON 3839 -1604
 TD 3870 -1635

PERFS: MARMATON PERF W/ 40/IT 3847-3852
 ACID 2000 GALS RET 400 GALS MCA,
 500 GALS 154 REG
 SWFR 780 BBLs WTR & 5700 LBS SAND

LOG TYPES: 0-3870 CORL
 0-1650 CBND

NO CORES OR DSTS

OPER ADDRESS: 107 N MARKET, STE 1115, WICHITA, KS 67202
 CONTR: A L ABERCROMBIE GEOL: D C MARCHANT

ID CHANGES: OPER NAME CHGD FROM LANSING ENERGY

KS 11-050791

Copyright 1991 Petroleum Information Corporation