

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-195-21,567-00-00
SW SW NE, Sec. 21, T 11 S, R 21 W
2970 ^{FSL} feet North of SE section line
2310 ^{FEL} feet West of SE section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5886

Lease Name Montague Well # 1

Operator: Chief Drilling Company
Name & 905 Century Plaza
Address Wichita, Ks. 67202

County Trego

Well Total Depth 3935 feet

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8 feet 296

Abandoned Oil Well Gas Well Input Well SWD Well D&A XX

Other well as hereinafter indicated

Plugging Contractor Warriar Drilling Company License Number 5883

Address Same as above

Company to plug at: Hour: PM Day: 16th Month: August Year: 1984

VERBAL PLUGGING ORDERS GIVEN TO Jerry Dinkel

(company name) Warriar Drilling Company (phone)

were: Order 210 lbs. 50/50 pozmix 6% gel 3% cal. cl., 1 sk flo-cel and 8 5/8" plug
Spot with drill pipe with no less than 36 vis. mud between all plugs, with good
circulation and no fluid loss.

Signed (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None XX

Operations Completed: Hour: 2:45 PM Day: 16th Month: August Year: 1984

ACTUAL PLUGGING REPORT

1st plug @ 3900 w/25 sks

2nd plug @ 1710 w/25 sks

3rd plug @ 980 w/100 sks 1 sk flo-cel

4th plug @ 310 w/40 sks

5th plug @ 40 w/8 5/8" plug 1/2 sk hull and 10 sks cmt

10 sks in Rat Hole

Remarks:

Cemented by Allied

RECEIVED STATE CORPORATION COMMISSION

AUG 27 1984
8-27-1984
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above plugging instructions were given as
and that I (did / did not) observe this plugging.

Signed Gilbert P. Leiker (TECHNICIAN)

INVOICED

DATE 8-29-84
INV. NO. 3407

8-24-84 27