

4-27

061838

6

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 195-22,011-00-00
SW, SEC. 22, T 11 S, R 21 W/Ex

990 feet from S section line
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8449

Lease Name Ehlenburg Well # 1

Operator: McNames and Patterson
Name & Address Box 20058

County Trego 129.19

Well Total Depth 3975 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 252 w/150 sks

Abandoned Oil Well Gas Well Input Well SWD Well O&A X

Other well as hereinafter indicated

Plugging Contractor Shields Drilling Co. License Number

Address Russell, Ks. 67665

Company to plug at: Hour: 1:30AM Day: 27 Month: April Year: 19 89

Plugging proposal received from Burton Berry

(company name) Shields Drilling (phone)

were: Order 190 sks 60/40 poz 6% gel 3% cc 1 sk F.C. and 8 5/8" plug.

Spot with drill pipe with no less than 36 vis mud between all plugs with good circulation and no fluid loss.

RECEIVED
STATE CORPORATION COMMISSION
STAFF
5-11-1989
MAY 11 1989

Plugging Proposal Received by Gilbert G. Scheck (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 1:30 AM Day: 27 Month: April Year: 19 89

ACTUAL PLUGGING REPORT 1st plug at Arb 3924' w/20 sks

2nd plug at 1750' w/20 sks

3rd plug at 975' w/100 sks 1 sk F.C.

4th plug at 300' w/40 sks

5th plug at 40' w/10 sks

10 sks in rathole 10 sks in mousehole

Remarks: Allied Cement

(If additional description is necessary, use BACK of this form.)

INVOICED
Observe this plugging.

Signed Gilbert G. Scheck (TECHNICIAN)

DATE 5-12-89

INV. NO. 24820

JUL 11 1989

4-27