

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

*KCC REPORT SPOT
RESEARCH*

API Well Number: 15-179-21146-00-00
Spot: W2W2NW Sec/Twnshp/Rge: 26-9S-26W
4080 feet from S Section Line, 4950 feet from E Section Line
Lease Name: ALVIN Well #: 1
County: SHERIDAN Total Vertical Depth: 4178 feet

Operator License No.: 30076
Op Name: ANDERSON, ANDY DBA A & A PRODU
Address: PO BOX 100
HILL CITY, KS 67642

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	4175	0	395 SX
SURF	8.625	253	0	290 SX
T1	2.875	4120		

135.79

Well Type: OIL UIC Docket No: Anderson, C.D. dba Anderson Date/Time to Plug: 02/03/2009 10:30 AM
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS Drilling
Proposal Rcvd. from: ANDY ANDERSON Company: A&A PRODUCTION Phone: (785) 421-6266

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 4% gel - 500# hulls.
Plug through casing.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/03/2009 12:30 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

8 5/8" surface casing set at 253' w/290 sxs cement.
5 1/2" production casing set at 4175' w/395 sxs cement.
TD 4178'. PBTD 4175'.
Alt II with 240 sxs - pumped from 4175' - 60 barrels drilling mud spacer and 150 sxs EA II
Cement in lower stage. Witnessed by KCC agent on 12/13/2005.
Connected to 5 1/2" production casing - pumped 60 sxs cement mixed with 500# hulls -
10 sxs gel and 220 sxs cement.
Max. P.S.I. 500#. S.I.P. 350#.
Connected to 8 5/8" surface casing. Pumped 15 sxs cement.
Max. P.S.I. 500#. S.I.P. 400#.

Perfs:

Top	Bot	Thru	Comments
4024	4027		
3966	3970		
3934	3936		

INVOICED

DATE 2/24/09
INV. NO. 2009061246

RECEIVED
KANSAS CORPORATION COMMISSION
FEB 18 2009
CONSERVATION DIVISION
WICHITA, KS

Remarks: SOS CEMENTING COMPANY-TICKET #327.

Plugged through: CSG

District: 04

Signed Darrel Dipman
(TECHNICIAN)

CM
PKG

replacement card
WILDCAT

CASTLE RESOURCES
SCHOENCHEN KS 67667

26-09S-26W
120' N, C W/2 W/2 NW

#1 ALVIN

site: 7-1/4 S & 1-1/2 W OF STUDLEY KS
contr: ANDERSON DRILLING #1
geol: JERRY D. GREEN
fr date 10/14/2005
spd date 12/05/2005
dig comp 12/12/2005
card issued 05/01/2006
last revised 02/19/2007
city: SHERIDAN
field: WC (BETHEL CEMETERY)
APR 15-179-21146
DISC

ELV: 2649 KB, 2644 GL LOG
tops.....depth/datum
ANH.....2301 +348
B/ANH.....2307 +342
HEEB.....3856 -1207
LANS A.....3892 -1243
LANS B.....3922 -1273
LANS C.....3933 -1284
LANS D.....3942 -1293
LANS E.....3958 -1309
LANS F.....3962 -1313
LANS G.....3984 -1335
LANS H.....4010 -1361
LANS I.....4023 -1374
LANS J.....4048 -1399

IP status
OIL, P 20 BO & 40 BWP, LKC 3934-4027 OA, 02/03/2006
LANS K.....4067 -1418
LANS L.....4069 -1440
BKC.....4125 -1476
LTD.....4178 -1529
RTD.....4178 -1529
INFO RELEASED: 2/19/2007 - WAS OIL WELL - TIGHT HOLE
CSG: 8-5/8" 253 / 290 SX (ALT 2), 5-1/2" 4175 / 395 SX
COMMENT: MI & RURT 12/5/2005
NO CORES

COPYRIGHT 2006
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS

(over)

CASTLE RESOURCES
SCHOENCHEN KS 67667

26-09S-26W
120' N, C W/2 W/2 NW

#1 ALVIN

DST (1) 4003-4035 (LANS H, W/STR PKR), / 30-30-30-30, (1ST OP) WB TO SB/2", ISI: 4 INCH BLO BK, (2ND OP) WB TO SB/2", FSI: 2 INCH BLO BK, 1520' GIP, REC 775' TF: 650' CLEAN OIL (GR 39), 125' GSY MDY OIL (35% G, 45% OIL, 20% M) ISIP 861# FSIP 779# IFP 60# -181# FFP 188# -261# IHP 1976# FHP 1945# BHT 120'

DST (2) 3940-3974 (LANS D-F), / 30-30-30-30, (1ST OP) WB TO SB/4", ISI: SURF BLO BK, (2ND OP) WB TO SB/7", FSI: SURF BLO BK, 795' GIP, REC 755' TF: 124' GSY MDY WCO (15% G, 45% OIL, 30% W 10% M), 496' GSY MDY WCO (10% G, 58% OIL, 12% W, 20% M), 135' GSY MDY WCO (10% G, 53% OIL, 13% W, 24% M) ISIP 984# FSIP 963# IFP 45# -211# FFP 227# -324# IHP 1977# FHP 1949# BHT 122'

DST (3) 3884-3906 (LANS A), / 45-30-0-0, WB THRU-OUT, 1/2 INCH BLT TO 1-1/4 INCH IN BKT ON BOTH OPENS, NB ON BOTH SI, REC 55' SLI OIL & GCWM (5% G, 5% OIL, 40% W, 50% M) ISIP 952# IFP 23# -43# IHP 1919# FHP 1907# BHT 120'

DST (4) 4036-4178 (LANS I-L), / 45-45-45-45, (1ST OP) WB THRU-OUT, 1/2 INCH BLT TO 1-1/2 INCH IN BKT, ISI: NB, (2ND OP) WB THRU-OUT, 1/4 INCH BLT TO 1 INCH IN BKT, FSI: NB, REC 30' OCM (10% OIL, 90% M) ISIP 686# FSIP 119# IFP 28# -42# FFP 31# -37# IHP 1995# FHP 1915# BHT 121'

TRGT ZN: LKC (OIL), PTD 4150 (LKC), MICT (1/25/2006) - CO, PF (LANS I) 4024-4027, W / 6 SPF, AC 1000 GAL (15% HC2), SWB LD, SO, PF (LANS F) 3966-3970, W / 6 SPF, AC 1250 GAL (15% HC2), SWB LD, SO, PF (LANS C) 3934-3936, W / 6 SPF, AC 1250 GAL (15% HC2), SWB LD, SO, SET 2-7/8" TBG AT 4120, NO PKR, POP, IPP 20 BO & 40 BWP (GR 38), DOFP 2/3/2006, COMMINGLED