

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-20730-00-00
Spot: SEWSE Sec/Twnshp/Rge: 23-16S-11W
1650 feet from S Section Line, 1650 feet from E Section Line
Lease Name: BESTHORN Well #: 3
County: BARTON Total Vertical Depth: 3409 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3378	0	75 SX
SURF	8.625	235	0	160 SX

110.79

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/09/2009 9:00 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: KEVIN WILES SR Company: AMERICAN WARRIOR, INC. Phone: (620) 275-2963

Proposed Plugging Method: Ordered 260 sxs 60/40 pozmix - 4% gel - 400# hulls - 15 sxs gel.
Perfed at 1385' - 710' - 305'.

Plugging Proposal Received By: BRUCE BASYE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/09/2009 1:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Ran tubing to 3400' - tied to tubing - pumped 15 sxs gel - pumped 50 sxs cement with 100# hulls.
Pulled tubing to 1400' - pumped 150 sxs cement with 300# hulls - cement circulated to surface.
Pulled tubing - tied onto casing - pumped 45 sxs cement. S.I.P. 300#.
Tied to backside - pumped 15 sxs cement. S.I.P. 400#.

Perfs:

Top	Bot	Thru	Comments
3378	3409		

INVOICED
DATE 2-24-09
INV. NO. 2009061247

RECEIVED
KANSAS CORPORATION COMMISSION
FEB 18 2009
CONSERVATION DIVISION
WICHITA, KS

Remarks: SWIFT SERVICES, INC.-TICKET #15420.

Plugged through: CSG

District: 04

Signed Bruce Rodie
(TECHNICIAN)

CM

PK9

BERGMAN OIL COMPANY #3 BESTHORN 23-16-11W
 SE NW SE
 425 UNION CENTER, WICHITA, KS.
 CONTR BERGMAN DRILLING, INC. CTY BARTON

GEOL _____ FIELD KRAFT PRUSA :

+	+	+
+	+	+
+	+	+

 E 1919 KB CM 4/18/73 CARD ISSUED 6/7/73 IP P 25 BOPD + 50% WTR
 ARB 3378-3409
 API 15-009-20,730

SMP	TOPS	DEPTH	DATUM	
				8 5/8" 235/160sx; 5 1/2" 3378/75sx
HEEB		2946	-1027	DST(1) 3115-62/1', 120'GIP, 1200'GCW, BHP 768-768#/30", FP 78-533#
TOR		2962	-1043	
DOUG		2979	-1060	MICT, CO & DD TO 3409 TD 500 ACID REC LD & SWB 5BFPH 40%OIL, TSTG, POP N-T
BN L		3046	-1127	
LANS		3068	-1149	
CONG		3364	-1445	
ARB		3374	-1455	
RTD		3379	-1460	NO LOG
DDTD		3409	-1490	

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS