

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-171-20089-00-01  
Spot: W2W2NE Sec/Twnshp/Rge: 20-17S-31W  
1320 feet from N Section Line, 2310 feet from E Section Line  
Lease Name: BROOKOVER UNIT Well #: 5-20  
County: SCOTT Total Vertical Depth: 4160 feet

Operator License No.: 5363  
Op Name: BEREXCO, INC.  
Address: PO BOX 20380  
WICHITA, KS 67208

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1540		
CIBP		3840		WITH 2 SX CMT
PROD 4.5		4159	0	WITH 150 SX CMT
SURF 8.625		331		WITH 185 SX CMT

Well Type: EOR UIC Docket No: E19167.1 Date/Time to Plug: 01/05/2009 2:00 PM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY *Berexco Inc KCCPCT*  
Proposal Rcvd. from: WAYNE GERSTNER, FORE Company: BEREXCO Phone: (316) 772-1155

Proposed Plugging Method: CIBP @ 3900' WITH 2 SX CMT. CIBP @ 1550'. TEST CASING TO 750#. PERFORATE @ 1500'. PUMP 80 SX CMT + CASING VOLUME. 150 SX CMT DOWN ANNULUS

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 01/05/2009 3:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 3840' WITH 2 SX CMT. CIBP @ 1540'. PRESSURE TEST CASING TO 750#. PERFORATE @ 1500'. INJECTION RATE TEST 1 BPM @ 400#. PUMPED 80 SX CMT, 200# HULLS, & 70 SX CMT DOWN 4 1/2" CASING. SHUT IN PRESSURE 700#. PUMPED 100 SX CMT DOWN ANNULUS AT 100#. SHUT IN PRESSURE 25#.

Perfs:

Top	Bot	Thru	Comments
4032	4033		
4016	4018		
3980	3981		
3964	3968		

**INVOICED**  
DATE 2-24-09  
INV NO. 2009061248

RECEIVED  
KANSAS CORPORATION COMMISSION

FEB 19 2009

CONSERVATION DIVISION  
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

District: 01

RECEIVED

JAN 16 2009

KCC DODGE CITY

Signed

*Ken Jehlik*

(TECHNICIAN)