

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-055-21918-00-00
Spot: SE Sec/Twnshp/Rge: 8-22S-31W
1320 feet from S Section Line, 1320 feet from E Section Line
Lease Name: WINTERS Well #: 1-8
County: FINNEY Total Vertical Depth: 2790 feet

Operator License No.: 5055
Op Name: C. H. TODD, INC.
Address: 1000 N TYLER STE 100
WICHITA, KS 67212

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2780	0	WITH 450 SX CMT
SURF	8.625	425		WITH 275 SX CMT

90.68

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 02/04/2009 10:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: KENNY LANG Company: C.H. TODD INC. Phone: (316) 264-7566

Proposed Plugging Method: PUMP DOWN CASING WITH 200# HULLS & 125 SX CMT. FILL CASING TO SURFACE WITH CEMENT. CHECK BACKSIDE.

Plugging Proposal Received By: STEVE DURRANT Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/04/2009 11:30 AM KCC Agent: KEN JEHLIK

Actual Plugging Report:

FILL 4 1/2" CASING WITH CMT FROM 2728-0' USING 400# HULLS & 190 SX CMT. PRESSURED TO 750# & HELD. ATTEMPTED TO PUMP DOWN 4 1/2" X 8 5/8" TO 1000 PSI. FULL OF CMT.

Perfs:

Top	Bot	Thru	Comments
2712	2728		

INVOICED
DATE 2-24-09
INV. NO. 2009061250

RECEIVED
KANSAS CORPORATION COMMISSION
FEB 9 2009
CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

District: 01

RECEIVED

FEB - 9 2009

KCC DODGE CITY

Signed



(TECHNICIAN)