

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-22817-00-00
Spot: SESENW Sec/Twnshp/Rge: 9-30S-14W
2310 feet from N Section Line, 2310 feet from W Section Line
Lease Name: EDWIN LENKNER Well #: 1
County: BARBER Total Vertical Depth: 4650 feet

Operator License No.: 3532
Op Name: CMX, INC.
Address: 1551 N WATERFRONT PKWY STE 150
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4330		WITH 2 SX CMT
CIBP		4490		
CIBP		4522		
PROD	5.5	4649	2700	WITH 175 SX CMT
SURF	8.625	333		WITH 240 SX CMT

181.13

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 02/06/2009 1:00 PM
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION
Proposal Rcvd. from: MARK MORGENSTERN Company: CLARKE CORPORATION Phone: (620) 886-5665

Proposed Plugging Method: CIBP @ 4330' WITH 2 SX CMT. PLUG AT 720' WITH 50 SX CMT. PLUG AT 350' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/06/2009 2:15 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 4330' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. LAID DOWN 5 1/2" CASING AND RUN 2 3/8" TUBING TO PLUG THROUGH. 1ST PLUG AT 732' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 350' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4498	4502		

INVOICED
DATE 2-24-09
INV. NO. 2009061251

RECEIVED
KANSAS CORPORATION COMMISSION
FEB 19 2009
CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

RECEIVED
FEB 10 2009

Signed Stephen J. Pfeifer
(TECHNICIAN)

KCC DODGE CITY