

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-093-20525-00-00  
Spot: NE Sec/Twnshp/Rge: 21-22S-36W  
3938 feet from S Section Line, 1352 feet from E Section Line  
Lease Name: MANNING Well #: 1  
County: KEARNY Total Vertical Depth: 3115 feet

Operator License No.: 5317  
Op Name: FREEMAN, RUSSELL DBA CONTINENT  
Address: PO BOX 918  
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2560		WITH 2 SX CMT
CIBP		2850		
PROD	5.5	3143	0	WITH 250 SX CMT
SURF	8.625	413		WITH 225 SX CMT

101.24

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/12/2009 2:00 PM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: LOLO ORTIZ Company: BORDERLINE WELL SERVICE Phone: (620) 353-9016

Proposed Plugging Method: CIBP @ 2560' WITH 2 SX CMT. TEST CASING TO 750#. PERFORATE AT 930. PUMP 80 SX CMT-200# HULLS-90 SX CMT. IF NO CIRCULATION, 150 SX CMT DOWN ANNULUS

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 01/14/2009 3:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 2560' WITH 2 SX CMT. PRESSURE TEST 5 1/2" CASING TO 800#. HOLDING. PERFORATE @ 930'. 1/14/09: RIG UP ALLIED. INJECTION TEST 3 BPM @ 800 PSI. PUMP 80 SX CMT, 150# HULLS, & 90 SX CMT DOWN 5 1/2" CASING. SHUT IN PRESSURE 300#. 2ND PLUG PUMP 100 SX CMT & 75# HULLS DOWN ANNULUS. SHUT IN PRESSURE 50#.

Perfs:

Top	Bot	Thru	Comments
2661	2674		
2648	2660		
2615	2622		

INVOICED  
DATE 2-24-09  
INV. NO. 200906125

RECEIVED  
KANSAS CORPORATION COMMISSION

FEB 19 2009

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

CONSERVATION DIVISION  
WICHITA, KS

Plugged through: CSG

District: 01

RECEIVED  
JAN 16 2009  
KCC DODGE CITY

Signed Ken Jehlik (TECHNICIAN)

FORM CP 2/3