

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-20213-00-00
Spot: NENWSE Sec/Twnshp/Rge: 4-20S-12W
2310 feet from S Section Line, 1650 feet from E Section Line
Lease Name: DENKER B Well #: 1
County: BARTON Total Vertical Depth: 3434 feet

Operator License No.: 3309
Op Name: EAGLE PETROLEUM, INC.
Address: PO BOX 335
ELLINWOOD, KS 67526

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3431	0	100 SX
SURF	8.625	178	0	175 SX

111.61

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/05/2009 9:00 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: RON HICKEL Company: EAGLE PETROLEUM, INC. Phone: (620) 793-2037

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 4% gel - 500# hulls - 12 sxs gel.
Perfed at 1460' - 600' - 280'.

Plugging Proposal Received By: BRUCE BASYE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/05/2009 2:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Ran tubing to 3400' - pumped 12 sxs gel - pumped 70 sxs cement on bottom with 200# hulls.
Pulled tubing to 1450' - pumped 145 sxs cement with 300# hulls. Cement circulated to surface.
Pulled tubing. Tied onto casing - pumped 50 sxs cement.
Circulated out backside. S.I.P. 200#.

Perfs:

Top	Bot	Thru	Comments
3416	3424		
3396	3406		

INVOICED
DATE 2-24-09
INV. NO. 2009061253

RECEIVED
KANSAS CORPORATION COMMISSION
FEB 18 2009
CONSERVATION DIVISION
WICHITA, KS

Remarks: COPELAND CEMENTING COMPANY-TICKET #33848.

Plugged through: CSG

District: 04

Signed Bruce Rodie
(TECHNICIAN)

CM PKT

PETROLEUM, INC.


#1 DENKER "B"

4-20-12W
NE NW SE

Contr. GARVEY DRLG

Cty. BARTON

Geol. Pool IONKIN CONF



E. 1812 KB Cm. 3/19/68 Cp. 5/23/68 IPP 68 BOPD + 2%W

GRAV 36.3/ARB
3416-24

API 15-009-20,213

LOG Tops	Depth	Datum
ANHY	612	+1200
TOP	2642	- 830
HEEB	2988	-1176
TOR	3006	-1194
DOUG	3022	-1210
BRLM	3108	-1296
LANS	3123	-1311
BKC	3356	-1544
CONG	3366	-1554
SH ARB	3384	-1572
ARB	3394	-1582
TD	3432	-1620
DDTD	3434½	-1622½

Csg. 8" 178/175 SX

DST 3123-70/60", 1515' GIP, 120'
GCM O/S, BHP 272-159#, FP
23-34#

DST 3174-3205/60", 5' MD, BHP 11-
11#, FP 11-11#

DST 3324-75/60", 65' OSM, BHP 79-
68#, FP 34-68#

DST 3347-95/60", 70' SOCM, 70' OCM
BHP 1140-1140#, FP 45-91#

DST 3396-3410/60", 585' FREE OIL,
300' MO, BHP 1140-1098#, FP
23-193#

CODD 3434½, OH 3431-34½, A 250, 6
4.23 BFPH (20%W) PF 3416-24, MOD
"D" PKR 3427, 4.23 BFPH (8%W), POP

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS