

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-171-20145-00-00
Spot: SE Sec/Twnshp/Rge: 24-19S-33W
1320 feet from S Section Line, 1320 feet from E Section Line
Lease Name: TEETER Well #: 1
County: SCOTT Total Vertical Depth: 2775 feet

Operator License No.: 33812
Op Name: EL PASO E&P COMPANY, L.P.
Address: 1001 LOUISIANA ST
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1015		
CIBP		2100		WITH 2 SX CMT 90.19
PROD	4.5	2772	0	WITH 200 SX CMT
SURF	8.625	502		WITH 250 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 02/02/2009 10:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: LOLO ORTIZ Company: BORDERLINE WELL SVC Phone: _____

Proposed Plugging Method: PER KCC INSTRUCTIONS: (1) MIRU CU. CO TO 2600 +/- (2200' MIN) (2) CIBP W/ 25 SX CMT. C/O 2600 +/- (3) CIBP @ 1350' (4) PRESSURE TEST CSG TO 800 PSI +/- (5) PERF 4 HOLES C/O 1325+/- (6) TAKE INJECTION TEST (7) CMT W/ 80 SX FOLLOWED BY 200# HULLS FOLLOWED BY 90 SX CMT (LEAVE CSG FULL OF CMT) (8) ATTEMPT TO PUMP 150 SX DOWN 4 1/2" X 8 5/8" ANNULUS (9) PLATE & CUT OFF 3-4' BGL. BRING 300 SX 60/40 POZ 4% GEL, TWO 4 1/2 CIBP, PERF GUN + EXTRA GUN, ONE CMT RET/STINGER.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/03/2009 2:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PBTD 2350' W/JUNK IN HOLE. 1ST PLUG SET CIBP @ 2100' WITH 2 SX CMT. 2ND PLUG SET CIBP @ 1015'. TEST CASING TO 800 PSI. 3RD PLUG PERFORATED CASING AT 1000'. ESTABLISH RATE. PUMPED 90 SX CMT & 200# HULLS, & 190 SX CMT AFTER PUMPING 100 SX WELL STARTED CIRCULATING. COMPLETED JOB BY CIRCULATING CMT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
2705	2722		

INVOICED
DATE 2-24-09
INV. NO. 2009061254

RECEIVED
KANSAS CORPORATION COMMISSION

FEB 19 2009

CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/840 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

District: 01

RECEIVED
FEB - 9 2009
KCC DODGE CITY

Signed

Ken Jehlik

(TECHNICIAN)

Form CP-2/3