

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-055-00262-00-00
Spot: SW Sec/Twnshp/Rge: 31-22S-32W
1320 feet from S Section Line, 1320 feet from W Section Line
Lease Name: HOBART A Well #: 1
County: FINNEY Total Vertical Depth: 2615 feet

Operator License No.: 5208
Op Name: EXXONMOBIL OIL CORP
Address: 14950 HEATHROW FORREST PKWY P
HOUSTON, TX 77210

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2601	717	WITH 700 SX CMT
SURF	8.625	395		WITH 325 SX CMT 84.99

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 01/21/2009 1:00 PM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGIN Phone: (580) 854-6515

Proposed Plugging Method: PUMP 200# HULLS & 25 SX CMT. PLUG AT 1200' WITH 50 SX CMT. PLUG AT 700' WITH 40 SX CMT. PLUG AT 420' WITH 40 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 01/22/2009 2:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 200# HULLS & 25 SX CMT AT 2501' THROUGH TBG. 1ST PLUG AT 1200' WITH 50 SX CMT. 2ND PLUG AT 700' WITH 40 SX CMT. 3RD PLUG AT 480' WITH 40 SX CMT. 4TH PLUG AT 40' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2501	2562		

INVOICED
DATE 2-24-09
INV NO. 2009061256

RECEIVED
KANSAS CORPORATION COMMISSION
FEB 19 2009

CONSERVATION DIVISION
WICHITA, KS

Remarks: USED COMMON CEMENT BY SARGENTS.

Plugged through: TBG


District: 01

RECEIVED

FEB - 9 2009

KCC DODGE CITY

Signed



(TECHNICIAN)

