

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-171-20048-00-00  
Spot: S2SWNENE Sec/Twnshp/Rge: 20-19S-31W  
1200 feet from N Section Line, 1000 feet from E Section Line  
Lease Name: DEARDEN Well #: 1-20  
County: SCOTT Total Vertical Depth: 2772 feet

Operator License No.: 33476  
Op Name: FIML NATURAL RESOURCES, LLC  
Address: 410 17TH ST STE 900  
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1985		WITH 2 SX CMT
PROD	5.5	2750	0	WITH 175 SX CMT <b>90.09</b>
SURF	8.625	367		WITH 250 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/05/2009 10:00 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: EDDIE ABERCROMBIE Company: FIML NATURAL RESOURCES Phone: (303) 893-5073

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 01/05/2009 12:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

1ST PLUG SET CIBP @ 1985' WITH 2 SX CMT. COULD NOT GET DOWN PAST 2020'. TEST CASING TO 500# @ 1985'. PERFORATE @ 1525'. ALLIED TOOK INJECTION TEST 3 BPM @ 600#. PUMP 80 SX CMT, 160# HULLS, & 105 SX CMT. SHUT IN AT 600#. CASING STAYED FULL. PUMP 165 SX CMT DOWN ANNULUS. SHUT IN PRESSURE 50#.

Perfs:

Top	Bot	Thru	Comments
2750	2772	OH	

**INVOICED**  
DATE 2-24-09  
INV. NO. 2009061257

RECEIVED  
KANSAS CORPORATION COMMISSION

FEB 19 2009

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

CONSERVATION DIVISION  
WICHITA, KS

Plugged through: CSG

District: 01

RECEIVED

JAN 16 2009

KCC DODGE CITY

Signed

*Ken Jehlik*

(TECHNICIAN)

FORM CP-3/3