

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-025-20804-00-01
Spot: E2SE Sec/Twnshp/Rge: 19-33S-24W
1320 feet from S Section Line, 660 feet from E Section Line
Lease Name: MCCARTY Well #: 19-1
County: CLARK Total Vertical Depth: 5800 feet

Operator License No.: 5254
Op Name: MIDCO EXPLORATION, INC.
Address: 414 PLAZA DR STE 204
WESTMONT, IL 60559

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5335		WITH 2 SX CMT
CIBP		5510		
COND	20	78		WITH 10 SX GROUT 188.50
PROD	4.5	5799	1943	WITH 200 SX CMT
SURF	8.625	793		WITH 500 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 02/03/2009 9:00 AM
Plug Co. License No.: 30891 Plug Co. Name: LEIKER WELL SERVICE, INC.
Proposal Rcvd. from: DAVID MAYFIELD Company: MIDCO EXPLORATION Phone: (630) 655-2198

Proposed Plugging Method: CIBP @ 5335' WITH 2 SX CMT. PLUG AT 820' WITH 50 SX CMT. PLUG AT 330' WITH 50 SX CMT. PLUG AT 40-0' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/03/2009 10:45 AM KCC Agent: JERRY W. STAPLETON

Actual Plugging Report:

CIBP @ 5335' WITH 2 SX CMT. 1ST PLUG LOAD HOLE WITH GEL. PUMP 60 SX CMT AT 915'. 2ND PLUG AT 425' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT. CMT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
5416	5426		

RECEIVED
KANSAS CORPORATION COMMISSION
FEB 12 2009
CONSERVATION DIVISION
WICHITA, KS

INVOICED

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

DATE 2-18-09
INV. NO. 2009061232

Plugged through: CSG

District: 01

RECEIVED
FEB - 6 2009
KCC DODGE CITY

Signed

Jerry W. Stapleton
PERMIT (TECHNICIAN)