

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-039-21086-00-00
Spot: NENWNE Sec/Twnshp/Rge: 14-3S-27W
330 feet from N Section Line, 1650 feet from E Section Line
Lease Name: M & M BAILEY Well #: 1-14
County: DECATUR Total Vertical Depth: 3900 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N WATER STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	301		

) 26.75

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 02/08/2009 1:00 PM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: LARRY PICKNER Company: MURFIN DRILLING CO., INC. Phone: (316) 267-3241

Proposed Plugging Method: Ordered 220 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: MARVIN MILLS WitnessType: NONE
Date/Time Plugging Completed: 02/08/2009 3:30 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

1st. Plug at 2265' w/25 sxs.
2nd. Plug at 1450' w/100 sxs.
3rd. Plug at 350' w/40 sxs.
4th. Plug at 40' w/10 sxs.
Rathole with 30 sxs.
Mousehole with 15 sxs.

Perfs:

INVOICED
DATE 2-18-09
INV. NO. 2009061233

RECEIVED
KANSAS CORPORATION COMMISSION

FEB 17 2009


CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed



(TECHNICIAN)

CM

Form CP-2/3

FEB 11 2009

PKT