

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-20026-00-02
Spot: NWNWSE Sec/Twnshp/Rge: 14-15S-21W
2259 feet from S Section Line, 2403 feet from E Section Line
Lease Name: L J BRENNER Well #: 1
County: TREGO Total Vertical Depth: 4230 feet

Operator License No.: 5399
Op Name: AMERICAN ENERGIES CORPORATION
Address: 155 N MARKET STE 710
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	4229	0	w/125 sxs cmt
SURF	8.625	200	0	w/165 sxs cmt
TI	2.375	1062		

Well Type: SWD UIC Docket No: D28370.0 Date/Time to Plug: 01/30/2009 12:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: THAD STARR Company: AMERICAN ENERGIES CORPORAT Phone: (620) 793-2146

Proposed Plugging Method: Ordered 425 sxs 60/40 pozmix - 4% gel - 700# hulls.
DV Tool at 1658' w/425 sxs.
CIBP at 1550'. Drilled out with mud pump and swivel.
Ran into junk in the hole at 2848'. (Drilled two days).
Operator elected all cement plug.

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/30/2009 3:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Express Well Service RIH with tubing to 2848'.
Allied rigged to tubing - pumped 50 sxs 60/40 pozmix - 4% gel neat - followed with 30 sxs with 100# hulls mixed in.
Pulled tubing to 2063'. Allied rigged to tubing - pumped 250 sxs 60/40 pozmix - 4% gel with 400# hulls.
Pulled tubing to 1006'. Allied rigged to tubing - pumped 60 sxs cement with 100# hulls to circulate cement to pit area.
Pulled tubing - rigged to 5 1/2" casing with a swedge - pumped 25 sxs 60/40 pozmix - 4% gel with 100# hulls.
Max. P.S.I. 200#. S.I.P. 100#.
Rigged to 8 5/8" - pumped 10 sxs cement.
Max. P.S.I. 100#. S.I.P. 50#.

Perfs:

Top	Bot	Thru	Comments
4106	4107		
1180	1190		
1090	1100		

INVOICED
DATE 2-17-09
INV. NO. 2009061205

RECEIVED
KANSAS CORPORATION COMMISSION

FEB 09 2009

CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY-TICKET #34938.

Plugged through: TBG

District: 04

Signed 
(TECHNICIAN)

CM

FEB 02 2009



ALPHA OIL COMPANY, INC. #1 J.L. BRENNER 14-15-21^w
 Contr. UMFGA DRLG. NW NW SE
 Geol. GLEN THRASHER Cty. TREGO
 Pool BRENNER POOL OPENER
 E. 2269 KB Cm. 7/29/67 Cp. 8/24/67 IP 111 BOPD TR. WTP
 4106 CHER.

LOG Tops	Depth	Datum
	1607	+ 662
ANH	3654	-1385
HEEB	3698	-1429
LANS	3954	-1685
BKC	4034	-1765
FT SCOTT	4092	-1823
CHER	4195	-1926
MISS.		
TD.	4230	-1961

Csg. API 15-195-20,026
 8-5/8" 200/165; 5 1/2" 4229/125SX
 DST 4088-4125/35", 510' G&MCO
 840' GSY CLN O, 240' O&GCM,
 (GR 38) BHP 1235-1189#, FP
 165-608#
 DST 4125-45/30", 930' MW, BHP
 1235-1208#, FP 46-348#
 SLOT 4106; FU 2775' OIH/14 HRS
 N/W, SWB AT RATE 9.5 BOPH, 4
 HRS. POP

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS