

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-21594-00-00
Spot: NENWNE Sec/Twnshp/Rge: 24-19S-13W
4950 feet from S Section Line, 1650 feet from E Section Line
Lease Name: SCHARTZ Well #: 1
County: BARTON Total Vertical Depth: 3426 feet

Operator License No.: 7023
Op Name: KLIMA WELL SERVICE, INC.
Address: PO BOX 48
GREAT BEND, KS 67530

| String | Size | Depth (ft) | Pulled (ft) | Comment |
|--------|-------|------------|-------------|---------------|
| PROD | 4.5 | 3403 | 1392 | w/150 sxs cmt |
| SURF | 8.625 | 540 | 0 | w/300 sxs cmt |

111.35

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/03/2009 9:30 AM
Plug Co. License No.: 7023 Plug Co. Name: KLIMA WELL SERVICE, INC.
Proposal Rcvd. from: DENNIS KLIMA Company: KLIMA WELL SERVICE, INC. Phone: (620) 793-8888

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 500# hulls.

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/03/2009 4:15 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Klima Well Service sanded off bottom to 3052' and topped with 2 sxs cement.
Log Tech shot off casing at 2190' - casing did not come loose.
Re-shot casing at 1392'.
Pulled casing to 1250'. Allied rigged to casing - pumped 90 sxs 60/40 pozmix - 4% gel with 300# hulls mixed in.
Pulled casing to 720'. Allied rigged to casing - pumped 45 sxs 60/40 pozmix - 4% gel with 100# hulls mixed in.
Pulled casing to 350'. Allied rigged to casing - pumped 70 sxs 60/40 pozmix - 4% gel with 100# hulls mixed in to circulate cement to surface.
Pulled casing - topped off hole with 25 sxs cement - hole standing full.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 3216 | 3219 | | |

INVOICED
DATE: 2-17-09
INV NO: 2009061208

RECEIVED
KANSAS CORPORATION COMMISSION
FEB 09 2009

Remarks: ALLIED CEMENTING COMPANY-TICKET #33343.

CONSERVATION DIVISION
WICHITA, KS

Plugged through: CSG

District: 04

Signed: [Signature]
(TECHNICIAN)

CM

FEB 04 2009

Form CP-2/3

PET

