

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-20821-00-00
Spot: SESENW Sec/Twnshp/Rge: 22-14S-15W
3017 feet from S Section Line, 2989 feet from E Section Line
Lease Name: JACOBS Well #: 1
County: RUSSELL Total Vertical Depth: 3458 feet

Operator License No.: 31528
Op Name: KELSO, MIKE OIL, INC.
Address: PO BOX 467
CHASE, KS 67524

String	Size	Depth (ft)	Pulled (ft)	Comment
PKR		3218		
PROD	7	3288	0	w/150 sxs cmt <u>112.39</u>
SURF	10.75	218	0	w/140 sxs cmt
T1	2.375	3218		

Well Type: SWD UIC Docket No: D24964.0 Date/Time to Plug: 01/23/2009 1:30 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: KELSO, MIKE OIL, INC. Phone: (620) 938-2944

Proposed Plugging Method: Ordered 400 sxs 60/40 pozmix - 4% gel - 500# hulls - 21 sxs gel.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/23/2009 4:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing to 3200' - pumped 21 sxs gel - pumped 100 sxs cement with 500# hulls.
Pulled tubing to 1500' - pumped 300 sxs cement - cement circulated.
Pulled tubing out of well.
Topped off with 20 sxs cement.

Perfs:

INVOICED
DATE 2-18-09
INV. NO. 2009061210

RECEIVED
KANSAS CORPORATION COMMISSION
FEB 09 2009
CONSERVATION DIVISION
WICHITA, KS

Remarks: COPELAND CEMENTING COMPANY-TICKET #33235.

Plugged through: TBG

District: 04

Signed

Ray A. Dinkel

(TECHNICIAN)

CM


Form CP-2/3

FEB 02 2009

PKT

HILLENBURG OIL CO. #1 JACOBS SWD 22-14-15W
 116 S. LYNN LANE RD. BROKEN ARROW, OK. SE SE NW
 CONTR B & B DRLG., INC. CTY RUSSELL

GEOL DON MELLAND FIELD WC (1/8 W OF GORHAM;
 SEP BY DRY HOLES)
 E 1800 RB CM 12/6/75 CARD 3/25/76 IP SWD
 GRAN 3288-3458



API 15-167-20, E21

SMP	TOPS	DEPTH	DATUM
HEEB	2945	-1145	
TOR	2564	-1164	
LANS	3003	-1203	
ARB	3276	-1476	
GRAN	3442	-1642	
RTD	3458	-1658	

10 3/4" 218/150sx, 7" 3288/150sx
 NO LOG
 NO DST'S
 MICT - CO, AC - INJ RATE SATIS

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS