

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-01409-00-01
Spot: SESENW Sec/Twnshp/Rge: 15-9S-21W
2970 feet from S Section Line, 2970 feet from E Section Line
Lease Name: TREXLER Well #: 7
County: GRAHAM Total Vertical Depth: 3703 feet

Operator License No.: 33190
Op Name: NOBLE ENERGY, INC.
Address: 100 GLENBOROUGH DR STE 100
HOUSTON, TX 77067

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3600		
PROD	6.125	3664	0	300 SX <u>120.35</u>
SURF	10.75	247	0	240 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/29/2009 10:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: JAMES POMMENOHN Company: NOBLE ENERGY, INC. Phone: (785) 625-5317

Proposed Plugging Method: Ordered out 500 sxs 60/40 pozmix - 4% gel - 13 sxs gel - 700# hulls - 6 sxs c.c. on the side.
No squeezed records: Perforate 1725' - 950' - 150'.
CIBP at 3600' on 11/24/2003.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/30/2009 4:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perforated two holes each at 1725' - 950' - 150'.
01/29/2009 - Ran tubing to 3559'. Allied mixed 13 sxs gel - followed with 100 sxs 60/40 pozmix - 4% gel with 3% c.c. with 300# hulls.
Attempted to pull tubing - stuck - parted tubing line. Shut down.
01/30/2009 - Repaired rig. Perf Tech backed tubing off at 2393'.
Pulled tubing out. Inspected. Ran back to 1747'.
Allied pumped 175 sxs 60/40 pozmix - 4% gel - cwc. PTOH. Squeezed 175 sxs cement with 400# hulls.
Max. P.S.I. 100#. S.I.P. 0#. Casing full.
Hooked up to backside - pumped 50 sxs cement.
Max. P.S.I. 100#. Blew hole in 10 3/4" Braden head - surface pipe full of cement.
Note: 1166' of 2 7/8" is left in bottom of hole.

Perfs:

Top	Bot	Thru	Comments
3684	3685		
3602	3607		
3586	3592		
3562	3566		
3549	3552		
3526	3531		
3476	3482		
3468	3473		
3450	3454		
3431	3441		
3395	3401		

INVOICED
DATE 2-18-09
INV. NO. 2009061212

RECEIVED
KANSAS CORPORATION COMMISSION

FEB 09 2009

CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed Richard Williams
(TECHNICIAN)

CM

Form CP-2/3

FEB 04 2009

[Handwritten signature]

ELYSIUM ENERGY LLC
DENVER CO 80202

15-09S-21W
SE SE NW

#7 TREXLER, O. E. OWWO

site 1 N & 4-1/2 W OF PALCO KS
contr: FISCHER WELL SVC

cty: GRAHAM
field MOREL

API 15-065-01409

well: NONE
fr data 01/13/2003 spd date 09/25/2002 drg comp 09/25/2002 card issued 01/13/2003 last revised 01/13/2003

E.L.V: 2223 DF SMP
tops.....depth/datum
ANH.....1690 +533
B/ANH.....1730 +493
ARB LM.....3682 -1459
FBTD.....3685 -1462
TD OLD.....3688 -1465
DDTD OLD.....3703 -1480

IP status
OIL, LKC 3468-3531 OA, ARB 3684-3685 , 10/14/2002
OLD INFO: OPERATOR WAS CONTINENTAL OIL CO, Z
TREXLER, O. E., SPD 08/09/1946, 09/11/1946 (10-3/4" 2470' 6"
3684) OIL, P 3,000 BOPD, NW, ARB 3684-3703
10/01/1946(CARD ISSUED 09/01/1947)
CONTR: UNKNOWN
COMMENT: REDESCRIBED LOC - IS ALSO 330' FSL &
330' FEL, NW/4; WAS TEMP AIR IOG 18669
DRLR SD ZNS: 900-980
NO CORES OR TSTS
MICT - CO TO 3688, (ARB OH), FU 2900' OIL, NW, NAT, DD
3703 TD, SWB 190 BO/6 HRS, NAT, POP, STATE ALLOW IPP
3000 BOPD, NW (DEPTHO), 10/1/1946

COPYRIGHT 2003
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS

(over)