

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-083-10340-00-00  
Spot: NWNW Sec/Twnshp/Rge: 13-23S-23W  
660 feet from N Section Line, 660 feet from W Section Line  
Lease Name: LIPPOLDT E F - B Well #: 3  
County: HODGEMAN Total Vertical Depth: 4565 feet

Operator License No.: 5030  
Op Name: VESS OIL CORPORATION  
Address: 1700 WATERFRONT PKWY BLDG 500  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
DVT		1233		WITH 575 SX CMT TOC @ 500'
PROD	4.5	4540	0	WITH 100 SX CMT
SURF	8.625	253		WITH 200 SX CMT <b>148.36</b>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/04/2009 10:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: AL TOVAR Company: MIKE'S TESTING & SALVAGE, INC. Phone: (620) 938-2537

Proposed Plugging Method: SAND 50' ABOVE OPEN HOLE & 5 SX CMT. PERFORATE AT 450'. RIH TO 1206'. LOAD HOLE CIRCULATE CMT TO SURFACE. SHUT IIN CASING PUMP DOWN ANNULUS.

Plugging Proposal Received By: STEVE DURRANT Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 02/05/2009 11:15 AM KCC Agent: LINDLEY REIMER

Actual Plugging Report:

SAND BACK TO 4400' & 4 SX CMT. PERFORATED 4 1/2" @ 450'. RIH W/TBG TO 1260'. LOAD HOLE WITH GEL WATER, PUMPED 150 SX CMT. LOST CIRCULATION. PULLED UP TO 1200'. PUMPED 35 SX CMT. DID NOT CIRCULATE. SHUT DOWN FOR 4 HOURS TO LET CMT SET. RIH TO 1700' W/O TAGGING CMT. POOH. RIH TO 1200'. PUMPED 60 SX CMT. NO CIRCULATION. SDON. 2/5/09: RIH W/TBG. TAG CMT AT 1571'. PULLED UP TO 1200'. LOADED HOLE WITH GEL WATER. PUMPED 100 SX CMT. CIRCULATED 10 SX CMT TO THE PIT. TIED ONTO BACKSIDE. PUMPED 100 SX CMT INTO 8 5/8" ANNULUS. SHUT IN PRESSURE 400#. TOPPED OFF 4 1/2".

Perfs:

Top	Bot	Thru	Comments
4546	4565		
4540			SQZ'D MISS DOLO
4527	4534		MISS B

INVOICED  
DATE 2-18-09  
INV. NO. 2009061217

RECEIVED  
KANSAS CORPORATION COMMISSION

FEB 09 2009

CONSERVATION DIVISION  
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND.

Plugged through: TBG

District: 01

RECEIVED  
FEB - 6 2009  
KCC DODGE CITY

Signed \_\_\_\_\_

(TECHNICIAN)

Form CP-279