

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-00024-00-00
Spot: SWSWNW See Twnshp/Rge: 19-11S-20W
2970 feet from S Section Line, 4950 feet from E Section Line
Lease/Unit Name: VANCE Well Number: 1
County: ELLIS Total Vertical Depth: 3844 feet

Operator License No.: 5893
Op Name: PRATT WELL SERVICE, INC.
Address: PO BOX 847
PRATT, KS 67124

Production Casing Size: 5.5 feet: 3832 200 SX
Surface Casing Size: 8.625 feet: 257 150 SX

12493

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/21/2003 12:00 PM
Plug Co. License No.: 32810 Plug Co. Name: PROFESSIONAL PULLING SERVICES LLC
Proposal Rcvd. from: LLOYD GATES Company: PRATT WELL SERVICE, INC. Phone: (620) 672-2531

Proposed Plugging Method: Ordered 250 sxs cement and 500# hulls.

Plugging Proposal Received By: BRUCE BASYE Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 10/21/2003 1:00 PM KCC Agent: ROGER MOSES

Actual Plugging Report:

5 1/2" casing at 3832' w/200 sxs cement. 8 5/8" set at 257' w/150 sxs cement.
Ran tubing to 1404' (tubing fish at approximately 1500') - spotted 135 sxs cement with 300# hulls, followed with 25 sxs cement and 400# hulls to circulate.
Pulled all tubing - squeezed 5 1/2" casing with 20 sxs cement with 200# hulls to 500#.
Blew hole in casing above braden head - removed cementing tool.
Cement remained at top of casing.
Tied to 8 5/8" x 5 1/2" annulus - pressured up to 350# - took no cement.
Total of 155 sxs 60/40 pozmix - 10% gel - 500# hulls.

RECEIVED
10-30-2003
OCT 30 2003
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY. KELLER TANK-WATER.

Plugged through: TBG

District: 04

Signed Roger Moses
(TECHNICIAN)

HP.

INVOICED
DATE 10-30-03
WEL NO 2004060701

10-27-2003
OCT 27 2003

IMPERIAL PETROLEUM CO

#1

VANCE

19-11-20W
SW SW NW

Contr. O & M DRILLING COMPANY

ELLIS

County

E 2232

Comm

Comp

2-8-52

IP

316 BOPD (LANS)
PHY POT

Tops	Depth	Datum
TOP	3268	-1036
HEEB	3484	-1252
LANS	3521	-1289
CONG	3779	-1517
ARB	3831	-1599
T.D.	3844	-1612

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

Casing

5" 3832

DST 3521-59, 1 HR, 35" MJD:
DST 3559-81, 1 HR, 10' FREE
OIL, 60" OIL CUT MUD: 8HP 651#
DST 3584-3612, 45 MIN, 480'
GASSY OIL: 8HP 1200#
DST 3670-3725, 1 HR, 160'
MUDDY OIL, 130' FREE OIL:
8HP 1010# ACID 500: WTR:
PB 3740: PERF 48 S, 3708-
3720: ACID 4000: 20 BOPD
PB 3628: PERF 3610-14: SQZ

NICKELSON NW POOL

