

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-159-30052-00-00  
Spot: NESESE Sec/Twnshp/Rge: 17-20S-10W  
1040 feet from S Section Line, 399 feet from E Section Line  
Lease Name: RICK Well #: 3  
County: RICE Total Vertical Depth: 3376 feet

Operator License No.: 31327  
Op Name: PAULEY, GARY DBA PAULEY OIL  
Address: 314 5TH ST  
CLAFLIN, KS 67525

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3375	1810	100 SX
SURF	8.625	197		160 SX

109.72

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/06/2009 1:00 PM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE INC Phone: (620) 562-8088

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: GREG EVES WitnessType: PARTIAL  
Date/Time Plugging Completed: 02/06/2009 3:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

SAND PERFS TO 3070' AND CAP WITH 5 SX'S CEMENT. CUT CASING OFF AT 1810' AND PULL TO 1300' AND PUMP 35 SX'S CEMENT. PULL CASING ON OUT & TAG CEMENT @ 1300' WITH TUBING. PULL TUBING TO 900' & PUMP 35 SX'S. PULL TUBING TO 250' & CIRCULATE CEMENT TO SURFACE. PULL TUBING OUT & TOP OFF.

Perfs:

Top	Bot	Thru	Comments
3262	3264		
3121	3126		

INVOICED  
DATE 2-19-09  
INV. NO. 2009061237

RECEIVED  
KANSAS CORPORATION COMMISSION

FEB 13 2009

Remarks: 60-40 POZ, 4 % GEL. COPELAND TICKET #C-35283.

Plugged through: TBG

District: 02

Signed Virgil Clothier  
(TECHNICIAN)

*PT*