

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Ellis County. Sec. 32 Twp. 11 Rge. 20 E/W
Location as "NE/CNW 1/4 SW 1/4" or footage from lines
SE SW NE

Lease Owner Icer Addis

Lease Name HUCK Well No. 1

Office Address Drawer 8038 - Wichita, Ks. 67208

Character of Well (Completed as Oil, Gas or Dry Hole) Dry Hole

Date Well completed 5-31-80 1980

Application for plugging filed 5-30 1980

Application for plugging approved 5-30 1980

Plugging commenced 5-31 1980

Plugging completed 5-31 1980

Reason for abandonment of well or producing formation _____


If a producing well is abandoned, date of last production 1980

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Marion Schmidt

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3855

Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above Section Plot

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Bottom plug set at 840' w/70 sacks 50/50 pozmix, 6% Gel thru drill pipe

Middle plug @ 240' w/20 sacks cement thru drill pipe

Top plug @ 40' w/20 sacks cement w/solid bridge of 1/2 sack hulls & 5 sacks cement in rat hole

RECEIVED
MAY 4 1980
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Duke Drilling Co., Inc. Great Bend

STATE OF Kansas COUNTY OF Barton, ss.
Bill Draney (employee of owner) or (owner or operator)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Bill Draney
Box 823 - Great Bend, Ks. 67530
(Address)

SUBSCRIBED AND SWORN TO before me this 2nd day of June, 19 80

Deborah M. Nagle
Notary Public.

My commission expires 4-11-1982

15-051-21973-00-00

DRILLERS' WELL LOG

DATE COMMENCED: May 23, 1980
DATE COMPLETED: May 31, 1980

Icer Addis
HUCK #1
SE SW NE Sec. 32-T11S-R20W
Ellis County, Kansas

0 - 75' Surface Soil, Post Rock
75 - 742' Shale
742 - 827' Sand
827 - 1090' Shale
1090 - 1294' Sand
1294 - 1593' Red Bed
1593 - 1645' Anhydrite
1645 - 2790' Shale & Lime
2790 - 3229' Lime & Shale
3229 - 3455' Lime
3455 - 3460' Shale
3460 - 3479' Lime & Shale
3479 - 3497' Lime & Shale
3497 - 3717' Lime
3717 - 3788' Lime & Shale
3788 - 3820' Lime, Chert, Shale
3820 - 3855' Dolomite
3855' RTD

ELEVATION: 2178 K.B.

FORMATION DATA

ANHYDRITE	1593
TOPEKA	3229
HEEBNER	3455
TORONTO	3479
LANSING- KC	3497
BASE K.C.	3717
MARMATON	3788
ARBUCKLE	3820
RTD	3855

SURFACE PIPE: Set used 8-5/8"
28# pipe at 244' with 165 sacks
50/50 pozmix, 2% Gel, 3% cc.

A F F I D A V I T

STATE OF KANSAS
COUNTY OF BARTON) ss

Bill Draney, of lawful age, does swear and state that the facts and
statements herein contained are true and correct to the best of his knowledge.

Bill Draney

Subscribed and sworn to before me this 2nd day of June 1980.

My Comm. Expires: 4-11-1982

Notary Public
Notary Public

6-4-1980