

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Trego SEC. 5 TWP. 11S RGE. 21 ~~W~~  
Location as in quarters or footage from lines:  
850' FWL, 1200' FNL, SW SE NW NW


Locate Well  
correctly on above  
Section Platt.

Lease Owner Petroventures, Inc.  
Lease Name Armbrister Well No. 1  
Office Address 65 S. Union Blvd., Suite 670, Lakewood, CO  
Character of Well (Completed as Oil, Gas or Dry Hole): dry hole  
Date Well Completed 11/23/83  
Application for plugging filed 11/23/83  
Plugging commenced 11/23/83  
Plugging completed 11/23/83

Reason for abandonment of well or producing formation (CL)  
dry hole

Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Carl Goodrow, Gil Scheck  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 3,926

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out.
				8-5/8"	295'	--

Describe in detail the manner in which the well was plugged, indicating where the mud  
fluid was placed and the method or methods used in introducing it into the hold. If cement  
or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet  
to \_\_\_\_\_ feet for each plug set.

- Mud to 3,870', 20 sx cement
- mud to 1,700', 100 sx cement
- mud to 850', 1 sx celloflake, 20 sx cement
- mud to 280, 40 sx cement,
- mud to 40', 10 sx cement,
- 10 sx cement in rathole
- 200 sx overall, 50/50 posmix
- 6% gel, 3% cc

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Allied Cementing Co., Inc.

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

Donald E. Hunt (employee of owner) or ~~(owner or operator)~~ of the  
above-described well, being first duly sworn on oath, says: That I have knowledge of the  
facts, statements, and matters herein contained and the log of the above-described well as  
filed and that the same are true and correct. So help me God.

(Signature) Donald E. Hunt  
Suite 250, 200 W. Douglas  
Wichita (Address) KS 67202

SUBSCRIBED AND SWORN TO before me this 9th day of December, 19 83

Kathleen L. Greger  
Kathleen L. Greger, Notary Public.  
STATE CORPORATION COMMISSION

My Commission expires: January 20, 1985

DEC 13 1983  
12-13-1983

CONSERVATION DIVISION  
Wichita, Kansas