


STATE OF KANSAS
STATE CORPORATION COMMISSION

15-195-00153-00-00

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Trego County. Sec. 6 Twp. 11 Rge. 21 (E) W (W)
Location as "NE/CNWxSWx" or footage from lines SE SE NW
Lease Owner PETROLEUM, INC.
Lease Name Armbrister Well No. 1
Office Address Route 2 Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed September 15, 1956
Application for plugging filed September 17, 1956
Application for plugging approved September 15, 1956
Plugging commenced September 15, 1956
Plugging completed September 15, 1956
Reason for abandonment of well or producing formation No Producing Zones

If a producing well is abandoned, date of last production None 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty Box 326, Hays, Kansas
Producing formation ----- Depth to top ----- Bottom ----- Total Depth of Well 3,850 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8" CD	216'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mud up with heavy mud to 210' pushed down 1/2 sack hulls to 210' followed by wooden plug. Placed 20 sacks cement through drill pipe on to plug. Mud up to 40' and placed 1/2 sack hulls at 40' followed by wooden plug and 10 sacks cement to base of well cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Garvey Drilling Co.
Address Route 2 Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.
Don Searle (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Don Searle
Route 2 Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 22nd day of September, 1956

My commission expires July 11, 1956
Zed J. Brown Notary Public.

PLUGGING
FILE SEC 6 T 11 R 21W
BOOK PAGE 100 LINE 40

9-25-1956

WELL LOG

15-195-00153-00-00

COMPANY Petroleum Inc.

SEC. 6 T. 11 R. 21

FARM Armbrister

NO. 1

LOC. SE-SE-NW


TOTAL DEPTH 3850'

COUNTY Trego Co., Kansas

COMM. 9-6-56

COMP. 9-15-56

CONTRACTOR Garvey Drilling Company



CASING 216' - 8 5/8"

ELEVATION 2047' DF

PRODUCTION D & A

FIGURES INDICATE BOTTOM OF FORMATIONS

170' - Clay & Shale	Heebner - 3407
216' - Blue Shale	Toronto - 3427
1360' - Sand & Shale	Douglas - 3440
1625' - Shells & Shale	Lansing - 3449
1665' - Anhydrite	Arbuckle - 3830
1885' - Shale & Shells	
2210' - Shale	
3415' - Lime & Shale	
3726' - Lime	
3776' - Lime & Chert	
3850' - Lime	

PLUGGING
 FILE SEC 6 T. 11 R. 21W
 BOOK PAGE 100 LINE 40

State of Kansas }
 County of Barton } ss:

I, Fred Bennett of Garvey Drilling Company
 upon oath state that the above and foregoing is a true and correct copy of the log of the #1 Armbrister well

Fred Bennett
9-29-1956

Subscribed and sworn to before me this 21st day of September 19 56

My Commission Expires: 11-12-58

Beaufort
 NOTARY PUBLIC