


29

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Trego County. Sec. 6 Twp. 11 Rge. 21 (E) (W)
Location as "NE/CNW&SW¼" or footage from lines SE SE SW
Lease Owner Leo J. Dreiling Oil Company
Lease Name Duetscher Well No. 1
Office Address Victoria, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) D & A
Date well completed 12-6-64 1964
Application for plugging filed 12-6-64 1964
Application for plugging approved 12-6-64 1964
Plugging commenced 12-6-64 1964
Plugging completed 12-6-64 1964
Reason for abandonment of well or producing formation -0-
If a producing well is abandoned, date of last production -0- 1964
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well W.L. Nichols
Producing formation -0- Depth to top 0 Bottom 0 Total Depth of Well 3834' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
SURFACE PIPE				8-5/8"	190'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with rotary mud to a depth of 540' where 1st plug was set using 20 sacks cement. Filling hole with rotary mud to a depth of 180' where 2nd plug was set using 20 sacks cement. Rotary mud was used to fill hole to a depth of 40' where 3rd plug was set using 10 sacks cement and filling hole to surface.

STATE CORPORATION COMMISSION

12-15-1964
DEC 15 1964

CONSERVATION DIVISION
WICHITA, KANSAS

Name of Plugging Contractor L. J. Dreiling & Sons, Inc.
Address Victoria, Kansas

STATE OF Kansas, COUNTY OF Ellis, ss.
L. Leo F. Dreiling, a partner (Employed by owner) or (Owner or operator)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leo F. Dreiling
LEO F. DREILING
Victoria, Kansas

SUBSCRIBED AND SWORN TO before me this 8th day of December, 1964

My commission expires October 26, 1968 Notary Public.

15-195-00452-00-00

L. J. DREILING and SONS, Inc.

VICTORIA, KANSAS

WELL LOG

Company Leo J. Dreiling Oil Company
Victoria, Kansas

Sec. 6 Twp. 11 Rng. 21

Farm Duetscher No. # 1

Location SE SE SW

Total Depth 3834'

County Trego

Comm. 11-28-64 Comp. 12-6-64

Elevation: 2131' D. F.

Contractor L.J. Dreiling & Sons, Inc.
Victoria, Kansas

2134 G. R.

Casing Record

Cement Record

Production:

190' 8-5/8"

125 sacks

RECORDED
12-15-1964
CORRECTION MADE BY
WORLD PARTIAL

Figures Indicate Bottom of Formations

0'	190'	Shale
190'	695'	Shale
695'	780'	Sand
780'	1290'	Shale
1290'	1327'	Sand
1327'	1606'	Shale
1547'	1647'	Anhy.
1646'	1656'	Shale
1656'	2285'	Shale & Shells
2285'	2459'	Shale & Shells
2459'	2562'	Shale & Shells
2562'	2730'	Shale & Lime
2730'	2845'	Shale & Lime
2845'	3024'	Lime & Shale
3045'	3113'	Lime & Shale
3113'	3216'	Lime & Shale
3216'	3343'	Lime & Shale
3343'	3432'	Lime
3432'	3475'	Lime
3475'	3477'	Lime
3477'	3550'	Lime
3550'	3608'	Lime
3608'	3667'	Lime
3667'	3737'	Lime
3737'	3789'	Lime
3789'	3810'	Lime
3810'	3834'	Lime
3834'		TD

STATE OF KANSAS)
)ss.
COUNTY OF ELLIS)

I, Leo F. Dreiling, of the L.J. Dreiling & Sons, Inc. upon oath states that the above and foregoing is a true and correct copy from the Daily Drilling Report from your Duetscher # 1.

Leo F. Dreiling
Leo F. Dreiling

Subscribed and sworn to before me this 10 day of December, 1964

Elmer Wells
NOTARY PUBLIC

My Commission Expires : October 26, 1968