


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Trego County. Sec. 7 Twp. 11S Rge. 21 (E) W (W)
Location as "NE/CNW&SW&" or footage from lines. NTT NTT NTT
Lease Owner Davis Bros. - Transit Corporation
Lease Name Hays Land Well No. 1
Office Address 1516 Liberty Bank Building, Oklahoma City, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) D. & A.
Date well completed June 20, 19 58
Application for plugging filed June 20, 19 58
Application for plugging approved June 20, 19 58
Plugging commenced June 20, 19 58
Plugging completed June 20, 19 58
Reason for abandonment of well or producing formation No Production

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19 ____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert P. Leiker, 805 W. Main, Victoria, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	161'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy drilling mud 600', set plug, cemented with 20 sacks of cement.

Filled hole with heavy drilling mud 155', set plug, cemented with 15 sacks of cement.

Filled hole with heavy drilling mud 40', set plug, cemented with 10 sacks of cement to bottom of cellar

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Transit Corporation
Address 1516 Liberty Bank Building, Oklahoma City, Oklahoma

STATE OF Oklahoma, COUNTY OF Oklahoma, ss.
Paul F. Gathers (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Paul F. Gathers

(Address)

SUBSCRIBED AND SWORN TO before me this 24th day of July, 19 58

My commission expires May 17, 1962

Mildred J. ...
Notary Public.

PLUGGING
FILE SEC 7 T 11 R 21W
BOOK PAGE 113 LINE 25

JUL 26 1958
6-26-1958
RECEIVED BY
WICHITA, KANSAS

15-195-00350-00-00

DRILLER'S WELL LOG

Davis Bros.-Transit Corporation - Hays Land # 1 located in
NW NW NW Sec. 7-11S-21W,
Trego, County, Kansas

Commenced: June 9, 1958
Completed: June 20, 1958
Elevation: 2118 K.B.

Casing 8 5/8" @ 161'
Cemented 150 sacks

<u>Formation</u>	<u>From</u>	<u>To</u>
Surface clay and shale	0	161
Shale	161	600
Shale and shells w/river gravel	600	700
Sand	700	840
Shale and shells	840	1130
Sand	1130	1250
Shale	1250	1575
Anhydrite	1575	1620
Shale and shells	1620	1905
Shale	1905	2090
Shale and lime streaks	2090	2220
Lime and shale streaks	2220	2525
Shale and lime streaks	2525	2675
Shale	2675	2910
Shale and lime streaks	2910	3025
Lime and shale streaks	3025	3091
Shale	3091	3240
Lime and shale	3240	3310
Lime	3310	3359
Lime and shale	3359	3420
Lime	3420	3465
Lime and shale	3465	3522
Lime	3522	3570
Lime and shale	3570	3630
Lime	3630	3678
Chert and lime	3678	3759
Arbuckle	3759	3808 TD

Summary of Formation

Heebner	3365'
Toronto	3385'
Lansing	3404'
B/Kansas City	3645'
Marmaton	3708'
Arbuckle	3759'

I hereby certify the forgoing to be a true and accurate Driller's Log of the formation encountered in the above well.

Subscribed and sworn to before me
this 24th. day of July, 1958.

My Commission expires May 17, 1962.

TRANSIT CORPORATION

By Paul E. Gathers

Mildred Dean
Notary Public

PLUGGING			
FILE	SEC. 7	T. 11	R. 21W
BOOK	PAGE 113	LINE	25

6-26-1958
CONSERVATION DIVISION
WARRANT OFFICE