


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Trego County. Sec. 10 Twp. 11S Rge. (E) 21 (W)

Location as "NE/CNWxSWx" or footage from lines. SW NW NW
Lease Owner Lee Phillips Oil Company & Braden Drilling, Inc.
Lease Name Taylor Well No. 1
Office Address 1620 Wichita Plaza, Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed November 28, 1967
Application for plugging filed November 28, 1967
Application for plugging approved November 28, 1967
Plugging commenced November 28, 1967
Plugging completed November 28, 1967
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well
Producing formation Depth to top Bottom Total Depth of Well 3735 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged at 800' w/70 sacks

Plugged at 210' w/20 sacks

Bridged at 40' to hold Kelly

Cement bottom of cellar w/40 sacks

Job completed at 9:30 A.M., 11-28-67

11-29-1967

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Braden Drilling, Inc.
Address 1620 Wichita Plaza, Wichita, Kansas 67202

STATE OF Kansas, COUNTY OF Sedgwick, ss. James Tasheff

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James Tasheff
1620 Wichita Plaza, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 28th day of November, 1967

My commission expires October 5, 1971 Carol J. Pearson Notary Public.

15-195-2052-00-00

DRILLER'S LOG

BRADEN DRILLING, INC.

#1 TAYLOR
SW NW NW
Sec. 10-11S-21W
Trego County, Kansas

Commenced: 11-20-67

Completed: 11-28-67

Set 5 joints 8-5/8" casing @ 208'
w/185 sacks Commom Cement, 2% Gel
and 2% Calcium Chloride

Plugged @ 800' w/70 sacks
Plugged @ 210' w/20 sacks
Bridged @ 40' to hold Kelly
Cemented bottom of cellar w/40 sacks

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>
Sand	0	110
Shale	110	210
Blue & Gray Shale	210	590
Shale	590	665
Sand	665	750
Sand & Shale	750	1055
Sand	1055	1275
Red Bed	1275	1485
Red Bed & Shale	1485	1537
Anhydrite	1537	1577
Shale & Shells	1577	1800
Shale & Shells	1800	2300
Shale & Lime	2300	2495
Lime & Shale	2495	2675
Shale & Lime	2675	2860
Shale & Lime	2860	3060
Shale & Lime	3060	3190
Shale & Lime	3190	3305
Lime	3305	3405
Lime	3405	3450
Lime	3450	3492
Lime	3492	3515
Lime	3515	3560
Lime	3560	3625
Lime	3625	3695
Arbuckle	3695	3735 T.D.


RECEIVED
STATE CORPORATION COMMISSION
11-30-1967
NOV 30 1967
CONSERVATION DIVISION
TOPEKA, KANSAS

I hereby certify that this is a true and correct log of the above captioned well as shown by the daily drilling reports.


James Tasheff

Subscribed and sworn to before me this 29th day of November, 1967.

My Commission expires October 5, 1971.


Carol J. Pearson, Notary Public