

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-195-21445-00-00

API NUMBER 15-195-21,445

LEASE NAME Taylor

WELL NUMBER 1

SPOT LOCATION S/2 N/2 SW

SEC. 10 TWP. 11S RGE. 21 ~~XXXX~~(W)

COUNTY Trego

Date Well Completed 2/20/84

Plugging Commenced 2/20/84

Plugging Completed 2/20/84

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR N-B Company, Inc.

ADDRESS P. O. Box 506  
Russell, KS 67665

PHONE # (913) 483-3518 OPERATORS LICENSE NO. 6111

Character of Well D&A  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes.

Which KCC/KDHE Joint Office did you notify? District #6

Is ACO-1 filed? No. If not, is well log attached? Yes.

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 3795'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		-0-	257'	8 5/8"	257'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Mud laden fluid @ 3795'-3700' 10 sks cement in rathole.

20 sks cement @ 3700'

20 sks cement @ 1600'

100 sks cement @ 700'

40 sks cement @ 240'

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Emphasis Oil Operations License No. 750

Address P. O. Box 506, Russell, KS 67665

STATE OF KANSAS COUNTY OF RUSSELL, ss.

Joe K. Branum

(employee of operator) or

(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

RECEIVED

STATE CORPORATION COMMISSION

2-27-1984  
FEB 27 1984

(Signature) *Joe K. Branum*


(Address) P. O. Box 506  
Russell, KS 67665

SUBSCRIBED AND SWORN TO before me this 23rd day of February, 1984

Wichita, Kansas

*Denise S. Reynolds*  
Denise S. Reynolds, Notary Public

My Commission expires: February 13th, 1985



15-195-21445-00-00

EMPHASIS OIL OPERATIONS

P. O. BOX 506

RUSSELL, KS 67665

DRILLERS LOG

OPERATOR: N-B Company, Inc.  
P. O. Box 506  
Russell, KS 67665

CONTRACTOR: Emphasis Oil Operations  
P. O. Box 506  
Russell, KS 67665

LEASE: Taylor WELL: #1

LOCATION: S/2 N/2 SW  
Section 10-11S-21W  
Trego County, KS

Rotary Total Depth: 3795'

Elevation: 2119 K.B.

Commenced: 2/13/84

Date Completed: 2/20/84

Casing: 8 5/8" @ 257' with 150 sacks cement

Status: Dry Hole


DEPTHS & FORMATIONS

(All measurements from K.B.)

Top Soil & Sand	30'	Shale	1915'
Post Rock, Sand & Shale	260'	Shale & Lime	2880'
Shale & Sand	988'	Lime	3083'
Sand, Shale & Redbed	1579'	Lime & Shale	3452'
Anhydrite	1619'	Lime (R.T.D.)	3795'

STATE OF KANSAS )  
                                  ) ss:  
COUNTY OF RUSSELL)


Joe K. Branum, of Emphasis Oil Operations, states that the above and foregoing is a true and correct log of the above captioned well, to the best of his knowledge.

  
\_\_\_\_\_  
Joe K. Branum

Subscribed and sworn to before me this 23rd day of February, 1984.

My Commission Expires: February 13th, 1985.

DENISE S. REYNOLDS  
NOTARY PUBLIC  
STATE OF KANSAS  
My Appointment Expires:  
2-13-85

  
\_\_\_\_\_  
Denise S. Reynolds, Notary Public

RECEIVED  
STATE CORPORATION COMMISSION  
2-27-1984  
FEB 27 1984  
CONSERVATION DIVISION  
Wichita, Kansas