

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Indian Oil Co., Inc.
Address: PO Box 209
Phone: (620) 886-3763 Operator License #: 31938
Type of Well: Gas oil KCCPT proper Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: May 1, 2008 (Date)
by: Steve Bond (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Cherokee Depth to Top: 4447 Bottom: 4464 T.D. 4499

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 047-20938 - 00 - 00
Lease Name: Knudson
Well Number: 1-22
Spot Location (QQQQ): SE - SE - NE -
2310 Feet from North / South Section Line
330 Feet from East / West Section Line
Sec. 22 Twp. 24 S. R. 18 East West
County: Edwards
Date Well Completed: October 30, 1981
Plugging Commenced: January 19, 2009
Plugging Completed: January 20, 2009

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Cherokee 4447-64	oil & gas	0	611'	8-5/8"	611'	0'
		0	4499	4-1/2"	4499'	2283'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Set CIBP @ 4400' w/ 2 sx cmt on plug.

Run 2-3/8" tbg to 1253. Pump 15 sx gel ahead of 50 sx cmt.

Pull tbg to 632' and pump 50 sx cmt.

Pull tbg to 62' and pump 35 sx cmt to surface

Name of Plugging Contractor: Eagle Well Service, DBA Bronco Energy Service License #: 7407


Address: PO Box 1597, Liberal, KS 67905-1597

Name of Party Responsible for Plugging Fees: Indian Oil Co., Inc.

State of Kansas County, Barber, ss.

Joscelyn Nittler

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) Joscelyn Nittler

(Address) 2507 SE US HWY 160, Medicine Lodge, KS 67104

SUBSCRIBED and SWORN TO before me this 12 day of February, 20 09

Tommi J. Cox My Commission Expires: 9-26-12
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

KANSAS CORPORATION COMMISSION
FEB 13 2009
CONSERVATION DIVISION
WICHITA, KS

[Handwritten initials]