

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. 132-33
LOCATION SW SW NE
SEC. 1 TWP. 9 RGE. 25

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease Clark

Operator Prime Dng Co
Petroleum Management Address 810 Central Bldg Wichita,

Field _____ County Graham

Total Depth 4065 Feet.

Plugging Contractor West Supply Co

Plugging Contractor's License No. 14

Address _____

(Describe briefly the manner in which the well was plugged)

8 5/8" at 250' circulated with cement - 5 1/2" at 4060' with 100
sax cement behind - P.B. tp 4024', perforated at 3800' - set
Halliburton plug at 3750', sand bridge and 4 sax cement set with
dump bailer - pulled 3300' 5 1/2" - filled hole with mud to 250',
set rock and 15 sax cement, mud to 35', set rock and 10 sax cement
to bottom cellar.

PLUGGING
FILE SEC 1 T 9 R 256
BOOK PAGE 132 LINE 33

RECEIVED
7-16-55

CONSERVATION DIVISION
Wichita, Kansas

Edwin Petty
District Conservation Agent
Date 7-15-55

CP-3