

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
2-7-72
FEB 7 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Okmar Oil Company,

Complete Address 1130 Vickers KSB&T Building, Wichita, Kansas.

Lease Name Clark Well No. 1

Location N/2-S/2-SE Sec. 1 Twp. 9 Rge. (E) (W) 25

County Graham Total Depth 4076'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Gabbert-Jones, Incorporated,

Address 830 Sutton Place, Wichita, Kansas License No.

Operation Completed: Hour 1:00 AM Day 4 Month 2 Year 1972

The above well was plugged as follows:

254'--8 5/8" Surface casing, cement circulated with 190 Sx.
Top of Dakota section @ 900'.

Circulated hole with heavy mud. Pulled DP to 1125' and displaced 110 Cu. Ft. cement
thru DP from 1125' to 800'. Pulled DP to 275' and displaced 30 Cu. Ft. cement thru
DP from 275' to 200'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 2/11/72
INV. NO. 5149-W

Signed: *W. L. D. [Signature]*
Well Plugging Supervisor