

DISTRICT CONSERVATION AGENT'S REPORT

*R*

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. \_\_\_\_\_

LOCATION NW NW SW

SEC. 1 TWP. 9 RGE 25 W

Dry Hole  Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 1 Lease Keith

Operator M. B. Armer Address Wichita, Kans

Field \_\_\_\_\_ County Graham

Total Depth <sup>4058</sup> 4119 <sup>KCC</sup> <sub>RT</sub> Feet.

(Describe briefly the manner in which the well was plugged)

10 3/4" at 200' circulated with cement - 7" at 4053' with  
50 sax cement behind. Perforations at 4041'.

Filled with chat to 4030', set 5 sax cement with dump  
bailer, pulled 1700' 7", filled hole with mud to 200',  
set rock and 20 sax cement, filled with mud to 30', set rock  
and 10 sax cement to bottom cellar.

RECEIVED  
STATE CORPORATION COMMISSION  
1-28-52  
JAN 28 1952  
Date 1-28-52  
District Conservation Agent  
Wichita, Kansas  
PLUGGING  
FILE SEC-1 T-9 R-20  
BOOK PAGE 141 LINE 2  
CONSERVATION DIVISION

*John J. [Signature]*

*F*