

16 KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
3-15-65
MAR 15 1965

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Empire Drilling Company,

Complete Address: 650 4th National Bank Building, Wichita, Kansas.

Lease Name Everette Keith Well No. 1

Location CS/2-SE-SW Sec. 1 Twp. 9 Rge. (E) (W) 25

County Graham Total Depth 3918 ^{RT} 3905 _{KCC}

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Above

Address: License No.

Operation Completed: Hour 2:00AM Day 9 Month 3 Year 1965

The Above well was plugged as follows:

174'--8 5/8" Surface pipe, cement circulated with 85 Sx.

Circulated hole with heavy mud, set plug @ 540' and displaced 20 Sx.

cement thru DP. Heavy mud to 180', set plug with 1/4 sack hulls and

displaced 20 Sx. cement thru DP. Heavy mud to 40', set plug with 1/2

sack hulls and 10 Sx. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 3/15/65

INV. NO. 811-W

Signed: N. L. Nichols
Well Plugging Supervisor