

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Empire Drilling Company,

Complete Address 650 Fourth National Bank Building, Wichita, Kansas.

Lease Name Minium Well No. 2

Location NW-NW-NW Sec. 1 Twp. 9 Rge. (E) (W) 25

County Graham Total Depth 4020'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Barnes & Sons Pipe Pulling Company,

Address Box #313, Russell, Kansas. License No. 9

Operation Completed: Hour 5:00 PM Day 7 Month 7 Year 1969

The above well was plugged as follows:

148'--8 5/8" Surface casing, cement circulated.

4019'--5 1/2" Production casing cemented on bottom with 100 Sx. Top perforations @ 3838'.

Sanded well back to 3800' and set 5 Sx. cement with dump bailer. Pulled 5 1/2" casing  
and squeezed well initially with 5 sacks hulls and 12 sacks gel and followed with 100  
Sx. cement from 925' to 600' then 11 sacks gel from 600' to 160' and followed with 20  
Sx. cement from 160' to 100' then 2 sacks gel from 100' to 30' and finally 10 Sx.  
cement from 30' to bottom of cellar. Maximum pump-in pressure--250#. Final shut-in  
pressure--100#. (Mudding and cementing operations by Halliburton).

I hereby certify that the above well was plugged as herein stated.

INVOICED

STATE CORPORATION COMMISSION

RECEIVED  
7-16-69  
JUL 16 1969

Signed: M. L. Nichols  
Well Plugging Supervisor

DATE 7/16/69

INV. NO. 99-W

CONSERVATION DIVISION  
Wichita, Kansas