

15-065-01627-0000

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT STATE CORPORATION COMMISSION

RECEIVED

12-10-74  
DEC 10 1974

CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Thornton E. Anderson  
Complete Address 340 R.H.Garvey Bldg., 300 W. Douglas, Wichita, Kansas 67202  
Lease Name Minium "A" Well No. 3  
Location NW SW NW Sec. 1 Twp. 9 Rge. (E) (W) 25  
County Graham Total Depth 4080'  
Abandoned Oil Well XX Gas Well      Input Well      SWD Well      D & A       
Other well as hereafter indicated       
Plugging Contractor Pipe Pullers, Inc.  
Address Box 486 Ellinwood, Kansas 67526 License No. 462  
Operation Completed: Hour 11:20 A Day 9 Month 12 Year 1974

The above well was plugged as follows:

Total Depth 4080' 8 5/8 csg set at 189' cwc 175 sk.  
5 1/2 csg set at 4079' cw 125 sk cem. Perf. (4005')  
Set 5 1/2 wood plug at 3900' -poured 20' sd -dumped 4 sk cmt. W/dump bailer. (3900-3850)  
Cutoff & recovered 1415' of 5 1/2 csg.  
Pumped down 8 5/8 csg with 20 sk gel & water -70 sk 50-50 poz 6% -15 sk gel & water -  
released 8 5/8 plug & pumped 50 sk 50-50 poz 6% W/100 lbs hulls.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 12/10/74  
INV. NO. 4210-W

Signed: Leo L. Massey  
Well Plugging Supervisor