

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
8-23-71
AUG 23 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Derrick-American Oil, Incorporated,

Complete Address 355 R. H. Garvey Building, Wichita, Kansas.

Lease Name Knobel Well No. 2

Location CNE Sec. 17 Twp. 9 Rge. (E) (W) 25

County Graham Total Depth 4112'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Gabbert-Jones, Incorporated,

Address 830 Sutton Place, Wichita, Kansas. License No.

Operation Completed: Hour 2:45 AM Day 19 Month 8 Year 1971

The above well was plugged as follows:

212'--8 5/8" Surface casing, cement circulated with 165 Sx.
Top of Dakota section @ 1150'.

Circulated hole with heavy mud. Pulled DP to 1375' and displaced 100 Sx. cement thru
DP from 1375' to 1050'. Pulled DP to 245' and displaced 25 Sx. cement thru DP from
245' to 170'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: H. L. Nichols
Well Plugging Supervisor

DATE 8-30-71
INV. NO. 4204-w