

15-065-205200-0000

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JAN 17 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Empire Drilling Company,

Complete Address 650 Fourth National Bank Building, Wichita, Kansas.

Lease Name Martin Well No. 1

Location 440' FNL & 440' FWL of SE/4 *NW NW SE* Sec. 17 Twp. 9 Rge. (E) (W) 25

County Graham Total Depth 440' 51.75

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Murfin Drilling Company,

Address 617 Union Center Building, Wichita, Kansas. License No.

Operation Completed: Hour 9:30 PM Day 12 Month 1 Year 1972

The above well was plugged as follows:

239'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 1150'.

Circulated hole with heavy mud. Pulled DP to 1375' and displaced 110 Cu. Ft. cement
thru DP from 1375' to 1050'. Pulled DP to 245' and displaced 30 Cu. Ft. cement thru
DP from 245' to 170'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: M. L. Nichole
Well Plugging Supervisor

INVOICED
DATE 1-18-72
INV. NO. 5026-W