

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 2 1971  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Derrick-American Oil, Incorporated,

Complete Address 355 R. M. Garvey Building, Wichita, Kansas.

Lease Name Pfeifer Well No. 1

Location NE-NE-SW Sec. 17 Twp. 9 Rge. (E) (W) 25

County Graham Total Depth 4090' <sup>27</sup> <sub>KLL</sub>

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated       

Plugging Contractor Gabbert-Jones, Incorporated,

Address 830 Sutton Place, Wichita, Kansas License No.       

Operation Completed: Hour 2:00 AM Day 30 Month 7 Year 1971

The above well was plugged as follows:

217'--8 5/8" Surface casing, cement circulated with 165 Sx.  
Top of Dakota section @ 1150'.

Circulated hole with heavy mud. Pulled DP to 1375' and displaced 100 Sx. cement thru  
DP from 1375' to 1050'. Pulled DP to 245' and displaced 25 Sx. cement thru DP from  
245' to 170'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to  
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 8-4-71

INV. NO. 4094-W

Signed: *K. L. Deibel*  
Well Plugging Supervisor