



KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 5 11-5-68 1968  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Rosen Oil Company,

Complete Address: 605 Sutton Place, Wichita, Kansas.

Lease Name Rome Well No. 1

Location NW-NW Sec. 27 Twp. 9 Rge. (E) (W) 25

County Graham Total Depth 4100

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: L. J. Dreiling & Sons, Incorporated,

Address: Victirna, Kansas. License No.     

Operation Completed: Hour 10:30 PM Day 2 Month 11 Year 1968

The Above well was plugged as follows:

255'--8 5/8" Surface casing, cement circulated with 150 Sx.  
Top of Dakota section @ 1075'.

Circulated hole with heavy mud. Pulled DP to 1300' and displaced 100 Sx. cement thru  
DP from 1300' to 975'. Pulled DP to 275' and displaced 20 Sx. cement thru DP from  
275' to 215'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to  
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 11/5/68  
INV. NO. 8757-41

Signed: M. L. Nichols  
Well Plugging Supervisor