

ORIGINAL

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

RECEIVED 2/6/09
KANSAS CORPORATION COMMISSION Form ACO-1
September 1999
Form Must Be Typed

FEB 06 2008

WELL COMPLETION FORM
WELL HISTORY - DESCRIPTION OF WELL & LEASE

CONSERVATION DIVISION
WICHITA, KS

Operator: License # 5822
Name: VAL Energy Inc.
Address: 200 West Douglas #520
City/State/Zip: Wichita, Kansas 67202
Purchaser: Maclaskey
Operator Contact Person: K. Todd Allam
Phone: (316) 263-6688
Contractor: Name: VAL Energy Inc.
License: 5822
Wellsite Geologist: Vern Schrag

CONFIDENTIAL

CONFIDENTIAL

FEB 06 2008

KCC

Designate Type of Completion:
 New Well Re-Entry Workover
 Oil SWD SIOW Temp. Abd.
 Gas ENHR SIGW
 Dry Other (Core, WSW, Expl., Cathodic, etc)

If Workover/Re-entry: Old Well Info as follows:
Operator: _____
Well Name: _____

Original Comp. Date: _____ Original Total Depth: _____
 Deepening Re-perf. Conv. to Enhr./SWD
 Plug Back _____ Plug Back Total Depth _____
 Commingled _____ Docket No. _____
 Dual Completion _____ Docket No. _____
 Other (SWD or Enhr.?) _____ Docket No. _____

11-13-2007 11-26-2007 12-14-2007
Spud Date or Date Reached TD Completion Date or
Recompletion Date Recompletion Date

API No. 15 - 007-23202-0000

County: Barber
NW SE SE NW Sec. 9 Twp. 34 S. R. 11 East West
2145 feet from S / (N) (circle one) Line of Section
2145 feet from E / (W) (circle one) Line of Section

Footages Calculated from Nearest Outside Section Corner:
(circle one) NE SE (NW) SW
Lease Name: Platt Well #: 1-6
Field Name: _____

Producing Formation: Mississippian
Elevation: Ground: 1367 Kelly Bushing: 1377
Total Depth: 4745 Plug Back Total Depth: 4697
Amount of Surface Pipe Set and Cemented at 267 Feet
Multiple Stage Cementing Collar Used? Yes No
If yes, show depth set _____ Feet
If Alternate II completion, cement circulated from _____
feet depth to _____ w/ _____ sx cmt.

Drilling Fluid Management Plan A/I INT 1070-08
(Data must be collected from the Reserve Pit)

Chloride content 21000 ppm Fluid volume 900 bbls
Dewatering method used hauled

Location of fluid disposal if hauled offsite:
Operator Name: VAL Energy Inc.
Lease Name: Talbott License No.: 5822
Quarter SW Sec. 9 Twp. 34S S. R. 11W East West
County: Barber Docket No.: D-30,033

INSTRUCTIONS: An original and two copies of this form shall be filed with the Kansas Corporation Commission, 130 S. Market - Room 2078, Wichita, Kansas 67202, within 120 days of the spud date, recompletion, workover or conversion of a well. Rule 82-3-130, 82-3-106 and 82-3-107 apply. Information of side two of this form will be held confidential for a period of 12 months if requested in writing and submitted with the form (see rule 82-3-107 for confidentiality in excess of 12 months). One copy of all wireline logs and geologist well report shall be attached with this form. ALL CEMENTING TICKETS MUST BE ATTACHED. Submit CP-4 form with all plugged wells. Submit CP-111 form with all temporarily abandoned wells.

All requirements of the statutes, rules and regulations promulgated to regulate the oil and gas industry have been fully complied with and the statements herein are complete and correct to the best of my knowledge.

Signature: K Todd Allam
Title: President Date: 2/5/08
Subscribed and sworn to before me this 5th day of February, 2008.
Notary Public: Brandi Wyer
Date Commission Expires: 2/24/2010

NOTARY PUBLIC - State of Kansas
BRANDI WYER
My Appt. Expires 2/24/2010

KCC Office Use ONLY
 Letter of Confidentiality Received
 If Denied, Yes Date: _____
 Wireline Log Received
 Geologist Report Received
 UIC Distribution



VAL ENERGY, INC.

200 W. Douglas, Suite 520
Wichita, Kansas 67202-3005

Office: (316) 263-6688 Fax: (316) 262-2512

RECEIVED
KANSAS CORPORATION COMMISSION

FEB 06 2008

CONSERVATION DIVISION
WICHITA, KS

CONFIDENTIAL

FEB 06 2008

KCC

February 6, 2008

Kansas Corporation Commission
130 s. Market Room 2078
Wichita, Kansas 67202-3802

To Whom It May Concern:

Please keep all information confidential pertaining to the Platt 1-9 located in the NW SE SE
NW Sec. 9-34S-11W, Barber County, Kansas

Sincerely,

K. Todd Allam



24 S. Lincoln Street
 P.O. Box 31
 Russell, KS 67665-2906

Voice: (785) 483-3887
 Fax: (785) 483-5566

RECEIVED
 KANSAS CORPORATION COMMISSION

FEB 06 2008

INVOICE

Invoice Number: 111286
 Invoice Date: Nov 20, 2007
 Page: 1

CONFIDENTIAL

FEB 16 2008

KCC

RECEIVED

NOV 24 2007

CONSERVATION DIVISION
 WICHITA, KS Ft

Bill To:
 Val Energy, Inc.
 200 W. Douglas
 STE #520
 Wichita, KS 67202

9208

Customer ID	Well Name/# or Customer P.O.	Payment Terms	
Val	Platt #1-9	Net 30 Days	
Sales Rep ID	Camp Location	Service Date	Due Date
	Medicine Lodge	Nov 20, 2007	12/20/07

Quantity	Item	Description	Unit Price	Amount
108.00	MAT	Common Class A	11.10	1,198.80
72.00	MAT	Pozmix	6.20	446.40
3.00	MAT	Gel	16.65	49.95
6.00	MAT	Chloride	46.60	279.60
189.00	SER	Handling	1.90	359.10
20.00	SER	Mileage 189 sx @.09 per sk per mi	17.01	340.20
1.00	SER	Surface	815.00	815.00
20.00	SER	Mileage Pump Truck	6.00	120.00
1.00	SER	Manifold Head Rental	100.00	100.00
1.00	EQP	Wooden Plug	60.00	60.00

Cement Surface Casing

ALL PRICES ARE NET, PAYABLE
 30 DAYS FOLLOWING DATE OF
 INVOICE. 1 1/2% CHARGED
 THEREAFTER. IF ACCOUNT IS
 CURRENT, TAKE DISCOUNT OF

\$ 376.90

ONLY IF PAID ON OR BEFORE

Dec 20, 2007

Subtotal	3,769.05
Sales Tax	128.19
Total Invoice Amount	3,897.24
Payment/Credit Applied	
TOTAL	3,897.24

376.90

3520.34

ALLIED CEMENTING CO., INC.

31299

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:

Medicine lake

DATE <i>11-16-07</i>	SEC. <i>9</i>	TWP. <i>34s</i>	RANGE <i>11W</i>	CALLED OUT <i>2:30p.m</i>	ON LOCATION <i>3:30p.m</i>	JOB START <i>9:30pm</i>	JOB FINISH <i>10:00pm</i>
LEASE <i>platt</i>	WELL # <i>1-9</i>	LOCATION <i>2814 Chedone BIKTP.</i>			COUNTY <i>Barber</i>	STATE <i>Ks</i>	
OLD OR <input checked="" type="radio"/> NEW (Circle one)				CONFIDENTIAL			

CONTRACTOR *Ual #3*

TYPE OF JOB *Surface*

HOLE SIZE *12 1/4* T.D. *270*

CASING SIZE *8 5/8* DEPTH *267*

TUBING SIZE _____ DEPTH _____

DRILL PIPE _____ DEPTH _____

TOOL _____ DEPTH _____

PRES. MAX _____ MINIMUM *-*

MEAS. LINE _____ SHOE JOINT *-*

CEMENT LEFT IN CSG. *15'*

PERFS. _____

DISPLACEMENT *16 BBB fresh*

EQUIPMENT _____

OWNER *Ual Energy*

CEMENT **KCC**

AMOUNT ORDERED *1805x60'40'2 + 3%cc*

FEB 06 2008

PUMP TRUCK CEMENTER *Mark C.*

352 HELPER *Darlin F.*

BULK TRUCK

367 DRIVER *Randy m.*

BULK TRUCK

_____ DRIVER _____

COMMON	<i>108</i>	<i>A</i>	@	<i>11.10</i>	<i>1198.80</i>
POZMIX	<i>72</i>		@	<i>6.20</i>	<i>446.40</i>
GEL	<i>3</i>		@	<i>16.65</i>	<i>49.95</i>
CHLORIDE	<i>6</i>		@	<i>46.60</i>	<i>279.60</i>
ASC			@		
			@		
			@		
			@		
			@		
			@		
			@		
HANDLING	<i>189</i>		@	<i>1.90</i>	<i>359.10</i>
MILEAGE	<i>20 x 189</i>		@	<i>.09</i>	<i>340.20</i>
TOTAL					<i>2674.05</i>

REMARKS:

*pipe bottom break Circ. pump bleed
fresh. mix 1805x60'40'2+3%cc.
Stop. release plus. Deep w/ fresh H₂O.
Deep to 252' w/ 16 BBB fresh.
Stop. Shut in. Release psi. Cement
did*

SERVICE

DEPTH OF JOB	<i>267</i>				
PUMP TRUCK CHARGE					<i>815.00</i>
EXTRA FOOTAGE			@		
MILEAGE	<i>20</i>		@	<i>6.00</i>	<i>120.00</i>
MANIFOLD	<i>Head Rental</i>		@	<i>100.00</i>	<i>100.00</i>
			@		
			@		

TOTAL *1035.00*

CHARGE TO: *Ual Energy*

STREET _____

CITY _____ STATE _____ ZIP _____

8 5/8" PLUG & FLOAT EQUIPMENT

<i>1-wooden plug</i>	@	<i>60.00</i>	<i>60.00</i>
	@		
	@		
	@		

ANY APPLICABLE TAX

WILL BE CHARGED TOTAL *60.00*
UPON INVOICING

TAX _____

TOTAL CHARGE _____

DISCOUNT _____ IF PAID IN 30 DAYS

SIGNATURE _____

PRINTED NAME _____

To Allied Cementing Co., Inc.
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

BASIC

energy services, L.P.

RECEIVED
KANSAS CORPORATION COMMISSION

FEB 16 2008
CONFIDENTIAL
CONSERVATION DIVISION
WICHITA, KS

TREATMENT REPORT

Customer: Val Energy, Incorporated Lease No. KCC Date: 1-26-07
 Lease: Pratt Well # 1-9
 Field Order # 16,762 Station Pratt Casing 5 1/2 14lb. Depth 4,735 Ft. County Barber State KS
 Type Job C.N.W. - Long String Formation 4-3-5 Legal Description W

PIPE DATA		PERFORATING DATA		FLUID USED		TREATMENT RESUME			
Casing Size <u>5 1/2 14lb.</u>	Tubing Size <u>1 1/2 11lb.</u>	Shots/Ft. <u>150 sacks</u>	<u>AA-2 with</u>	<u>.38 RATE</u>	<u>Friction Reducer</u>	<u>.25%</u>			
Depth <u>4,735 Ft.</u>	Depth <u>From Deformer</u>	<u>88</u>	<u>FLA-3</u>	<u>22, 108</u>	<u>Salt</u>	<u>1</u>	<u>Gas Blok</u>		
Volume <u>15.5 Bbl.</u>	Volume <u>From 5 Lb. / Sk. G. / sonite</u>			Min				<u>10 Min.</u>	
Max Press <u>1,500 P.S.I.</u>	Max Press <u>From To 15.31</u>	<u>6. / Gal.</u>	<u>5.79</u>	<u>3 gal. / sk.</u>	<u>1.38 cu. FT. / sk.</u>				
Well Connection <u>Mva Container</u>	Annulus Vol. <u>From To 25 sacks</u>	<u>60 / 40 Poz</u>	<u>HHP used</u>	<u>to plug Rat & Mouse</u>	<u>Notes</u>				
Plug Depth <u>4,735 Feet</u>	Packer Depth <u>From To</u>	<u>Flush</u>	<u>15 Bbl. Fresh Water</u>	<u>Gas Volume</u>	<u>Total Load</u>				

Customer Representative Russell Myers Station Manager David Scott Treater Clarence R. Messick

Service Units	<u>19,870</u>	<u>19,903</u>	<u>19,905</u>	<u>19,831</u>	<u>19,862</u>				
Driver Names	<u>Messick</u>	<u>Mattal</u>	<u>Shields</u>						

Time	A.M.	Casing Pressure	Tubing Pressure	Bbls. Pumped	Rate	Service Log
<u>7:00</u>						<u>Trucks on location and hold safety meeting.</u>
<u>9:00</u>						<u>Val Drilling start to run Regular Guide Shoe, Shoe joint with Auto-Fill Insert screwed into collar and a total of jts. 14lb./Ft. new 5 1/2" casing. Ran Turbaltizers on Collars #1, 2, 4, 6, 8 and 10.</u>
<u>11:30</u>						<u>Casing in well. Circulate for 1 hour.</u>
<u>12:17</u>		<u>300</u>		<u>20</u>	<u>6.5</u>	<u>Start Fresh water Pre-Flush.</u>
				<u>44</u>	<u>5</u>	<u>Start Super Flush II.</u>
				<u>47</u>	<u>5</u>	<u>Start Fresh water spacer.</u>
<u>12:26</u>		<u>300</u>		<u>84</u>		<u>Start Mixing 150 sacks AA-2 cement. Stop pumping. Shut in well. Wash pump and lines. Release plug. Open Well.</u>
<u>12:36</u>		<u>100</u>			<u>6.5</u>	<u>Start Fresh water Displacement.</u>
<u>12:49</u>				<u>100</u>	<u>5</u>	<u>Start to lift cement.</u>
<u>12:54</u>		<u>600</u>		<u>115</u>		<u>Plug down. Pressure up.</u>
		<u>1,500</u>				<u>Release pressure. Insert held.</u>
				<u>4-3</u>	<u>3</u>	<u>Plug Rat and Mouse holes. Washup pump truck.</u>
<u>1:30</u>						<u>Job Complete. Thanks, Clarence, Mike, Billy</u>

10244 NE Hiway 61 • P.O. Box 8613 • Pratt, KS 67124-8613 • (620) 672-1201 • Fax (620) 672-5383



FIELD ORDER 16962

Subject to Correction

Date	11-26-07	Customer ID		Lease	Platt	Well #	1-9	Legal	9-345-11W
				County	Barber	State	KS	Station	Pratt
C H A R G E	Val Energy, Incorporated			Depth		Formation		Shoe Joint	21.5 Feet
	Casing		14 1/2"	Casing Depth	4,735 Ft	TDL	4,750 Ft	Job Type	C.W.W. - Long String
	Customer Representative				Russell Myers		Treater		

AFE Number		PO Number		Materials Received by	X <i>[Signature]</i>	DLS
------------	--	-----------	--	-----------------------	----------------------	-----

Station Code	Product Code	QUANTITY	MATERIALS, EQUIPMENT, and SERVICES USED	UNIT PRICE	AMOUNT
P	D205	150sk	AA-2		\$2,479.50
P	D203	25 sk	60/40 Poz		\$ 267.75
P	C195	113Lb	FLA-322		\$ 932.25
P	C221	724Lb	Salt (Fine)		\$ 181.00
P	C243	36Lb	Defoamer		\$ 124.20
P	C244	43Lb	Cement Friction Reducer		\$ 258.00
P	C312	141Lb	Gas Blok		\$ 726.15
P	C321	750Lb	Gilsonite		\$ 502.50
P	C304	1,000Gal	Super Flush II		\$ 1,530.00
P	F101	6ea	Turbolizer, 5 1/2"		\$ 445.20
P	F143	1ea	Top Rubber Cement Plug, 5 1/2"		\$ 75.00
P	F191	1ea	Guide Shoe - Regular, 5 1/2"		\$ 186.65
P	F231	1ea	Insert Float Valve, 5 1/2"		\$ 175.00
P	E100	90mi	Heavy Vehicle Mileage, 1-Way		\$ 450.00
P	E101	45mi	Pickup Mileage, 1-Way		\$ 135.00
P	E104	367tm	Bulk Delivery		\$ 586.80
P	E107	175sk	Cement Service Charge		\$ 262.50
P	E891	1ea	Service Supervisor		\$ 150.00
P	R210	1ea	Cement Pumper: 4,501 Ft. To 5,000 Ft.		\$ 1,827.00
P	R701	1ea	Cement Head Rental		\$ 250.00
			Discounted Price =		\$ 9,697.38
			Plus Taxes		

CONFIDENTIAL
FEB 16 2008
RCC

CONFIDENTIAL
FEB 06 2008
KCC

