

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

OR  
FORMATION PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

Strike out upper line  
when reporting plug-  
ging off formations.

Russell County. Sec. 27 Twp. 11 Rge. (E) 15 (W)

Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines. NW/4 NW/4 NE/4

Lease Owner Musgrove Petroleum Corporation

Lease Name Boedecker Well No. 1

Office Address 407 K.F.H. Building, Wichita 2, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 4-14 19 48

Application for plugging filed 4-14 19 48

Application for plugging approved 4-14 19 48

Plugging commenced 4-14 19 48

Plugging completed 4-14 19 48

Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was com-  
menced? Agent

Name of Conservation Agent who supervised plugging of this well Representative at Great Bend

Producing formation Depth to top Bottom Total Depth of Well 330 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
None						

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Set wood plug at 160'  
Cemented on top of plug with 20 sacks of cement  
Filled with heavy mud to 20'  
Set another wood plug and cemented with 15 sacks of cement.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Musgrove Petroleum Corporation  
Address 407 K.F.H. Building  
Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

P. C. Musgrove (owner or operator) of the above-described well,  
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) P. C. Musgrove

407 K.F.H. Building, Wichita 2, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 26th day of April, 19 48.

Madine Jirels  
Notary Public.

My commission expires December 5, 1951



15-167-0044-00-00

CONTRACTOR'S VERIFIED LOG

Operator Musgrove Petroleum Co. Inc Farm Name Boedecker Well No. 1

Location NW 1/4 NE 1/4 Section 27 Twp 11- Range 15 N.

Pool Name \_\_\_\_\_ County Russell State Kan.

Commencement Date 4-5-48 Completion Date 4-14-48

LOG OF WELL

Depth		Formation	Deviation from Vertical (Degrees)	Remarks
From	To			
0	100'	Shale & Shells		
100'	163'	" "		
163'	330'	" "		
330	840'	Red Bed and Sand		
840'	885'	Red Bed and Shale		
885'	920'	Anhydrite		
920'	1085'	Shale & Lime		
1085'	1440'	Shale		
1440'	1595'	Lime & Shale		
1595'	1660'	Shale		
1660'	1930'	Lime & Shale		
1930'	2125'	Shale & Lime Shells		
2125'	2415'	Lime & Shale		
2415	2450'	Shale		
2450'	2540'	Lime, Shale & Shells		
2540'	3105'	Lime & Shale		
3105'	3294'	Lime		
3294'	3330	Arbuckle Lime T. D.		

Run Schlumberger at 3330' Dry Hole

Run 160' of 3 5/8" Spiral Weld new casing, set @ <sup>161'</sup> ~~152'~~ cemented with 100 sacks of cement at 11:30 A. M. on April 4-1948.

Well Plugged 4-14-1948.

The foregoing Well Log and other data are correct:

ADKINS DRILLING COMPANY, Inc.

By

*Jim Adkins*  
Pres.

4-27-1948

**PLUGGING**  
FILE SEC 27 T 11 R 15 W  
BOOK PAGE 23 LINE 3