

15-167-20135-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Russell County. Sec. 36 Twp. 11 Rge. 15 (E) W (W)

Location as "NE/CNW&SW&" or footage from lines SW-NE-SW

Lease Owner Leo J. Dreiling Oil Company

Lease Name Stielow Well No. 1

Office Address Route 2, Victoria, Kansas 67671

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 11-27 19 67

Application for plugging filed 11-27 19 67

Application for plugging approved 11-27 19 67


Plugging commenced 11-27 19 67

Plugging completed 11-27 19 67

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19 _____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above
Section Plat

Name of Conservation Agent who supervised plugging of this well Don Truan

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Pipe				8 5/8"	133'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

First plug was set at 500' with 100 sacks cement

Second plug was set at 200' with 25 sacks cement

Third plug was set at 40' with 10 sacks of cement

Cementing to bottom of cellar

RECEIVED
STATE CORPORATION COMMISSION

DEC 1 1967
12 - 1 - 1967

CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor L. J. Dreiling & Sons, Inc.

Address Route 2, Victoria, Kansas 67671


STATE OF Kansas, COUNTY OF Ellis, ss.
I, Leo F. Dreiling (employee of owner) or (~~conservation agent~~) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leo F. Dreiling

Leo F. Dreiling, Route 2, Victoria, Kansas 67671
(Address)

Subscribed and Sworn to before me this 29th day of November, 19 67



Joseph A. Hess
Notary Public.

My commission expires September 19, 1970

15-167-20135-00-00

L. J. DREILING and SONS, Inc.
VICTORIA, KANSAS

WELL LOG

Company	Leo J. Dreiling Oil Company Route 2 Victoria, Kansas 67671	Sec. 36	Twp. 11	Ang. 15
Farm	Stielow No. 1	Location	SW-NE-SW	
Total Depth	3290'	County	Russell	
Comm.	11-19-67 Comp-11-27-67	Elevation:	1740' K.B. 1739' D.F.	
Contractor	L. J. Dreiling & Sons, Inc. Route 2 Victoria, Kansas 67671		1735'	G.R.
	Casing Record 133' - 8 5/8"	Cement Record	Production: D & A	
			100 sacks cement	

Figures Indicate Bottom of Formations

0'	120'	Top Soil and Rock
120'	134'	Shale
134'	489'	Shale & Sand Streaks
489'	811'	Redbed
811'	849'	Anhy.
849'	860'	Shale & Shells
860'	1421'	Shale & Shells
1421'	1503'	Shale with lime Streaks
1503'	1698'	Lime
1698'	1890'	Lime
1890'	1973'	Lime
1973'	2055'	Shale & Lime
2055'	2227'	Lime
2227'	2442'	Lime & Shale
2442'	2680'	Shale & Lime
2680'	2780'	Lime & Shale
2780'	2870'	Lime & Shale
2870'	2947'	Lime
2947'	2973'	Lime
2973'	3032'	Lime
3032'	3075'	Lime
3075'	3133'	Lime
3133'	3211'	Lime
3211'	3240'	Conglomerate
3240'	3290'	Conglomerate
3290'	T.D.	


STATE OF KANSAS)
)ss
COUNTY OF ELLIS)

RECEIVED
KANSAS OIL AND GAS COMMISSION
12-1-1967
DEC 1 1967

I, Leo F. Dreiling, of the L. J. Dreiling & Sons, Inc., upon oath states that the above and foregoing is a true and correct copy from the Daily Drilling Report from your Stielow #1.
Victoria, Kansas

Leo F. Dreiling

LEO F. DREILING



Joseph A. Hess

JOSEPH A. HESS NOTARY PUBLIC

My commission expires: September 19, 1970