

15-051-~~10452~~-00-00
01722

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Ellis County, Sec. 12 Twp. 11S Rge. 16 (E) W (W)

Location as "NE/CNW/SW" or footage from lines N/2 NE/4 NE/4

Lease Owner Birmingham-Bartlett Drilling Co.

Lease Name BOWLBY Well No. 2

Office Address 300 Kaufman Building, Wichita, Kansas 67202

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed November 14, 19 64

Application for plugging filed (verbal) November 14, 19 64

Application for plugging approved (verbal) November 14, 19 64

Plugging commenced November 14, 19 64

Plugging completed November 14, 19 64

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation Depth to top Bottom Total Depth of Well 3445 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	173'	8-5/8"	173'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Top plug set at 40' with 10 sacks cement.
Center plug set at 170' with 20 sacks cement.
Bottom plug set at 480' with 1/4 sack hulls and 20 sacks cement.

11-19-1964
NOV 19 1964
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Birmingham-Bartlett Drilling Co.
Address 300 Kaufman Building, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Richard Hindery, partner of Birmingham-Bartlett Drilling Co., owner, operator & contractor
well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. BIRMINGHAM-BARTLETT DRILLING CO.
(Signature) By Richard Hindery Partner
300 Kaufman Building, Wichita, Kansas 67202 (Address)

SUBSCRIBED AND SWORN TO before me this 18th day of November, 19 64.

My commission expires October 2, 1966. Beverly Larson Notary Public.

15-051-~~10452~~-00-00
0122

BOWLEY NO. 2 WELL

LOCATION: N/2 NE/4 NE/4
Section 12-11S-16W
Ellis County, Kansas

SPUDDED: 11-7-64
DRILLING
COMPLETED: 11-14-64

OWNER, OPERATOR
and CONTRACTOR: Birmingham-Bartlett Drilling Co.
300 Kaufman Building
Wichita, Kansas 67202

SURFACE CASING: 8-5/8" surface casing cemented
at 173' with 165 sacks cement.

OIL STRING: None set. Dry hole.
Plugged 11-14-64.

LOG

(Figures indicate bottom of formation)

0 -	30	Surface clay and sand
	164	Shale and shells
	320	Shale
	410	Sand and shale
	765	Shale and shells
	1062	Shale, shells, and red bed
	1097	Anhydrite
	1775	Shale and shells
	2311	Lime and shale
	2575	Shale
	2780	Shale and lime
	2893	Lime
	3058	Shale and lime
	3173	Lime
	3245	Shale and lime
	3357	Lime
	3435	Shale and lime
	3445	Lime
	3445	Rotary total depth Dry hole

11-19-1964

The undersigned, Richard Hindery, one of the partners of Birmingham-Bartlett Drilling Co., hereby certifies that the above is a true and correct log of the Bowley No. 2 Well as shown in the daily drilling reports.

BIRMINGHAM-BARTLETT DRILLING CO.

By Richard Hindery
Richard Hindery, Partner

Subscribed and sworn to before me
this 18th day of November, 1964.

Beverly Larson
Beverly Larson, Notary Public
My commission expires October 2, 1966